Solid Waste Management Plan

Bulloch County
City of Statesboro
City of Brooklet
City of Portal
City of Register

Adopted August 5, 2008

TABLE OF CONTENTS

Section 1 Introduction 1.1 Planning area defined 1.2 Person responsible for plan 1.3 Overview of area covered	Page 4
Section 2 Waste Disposal Stream Analysis 2.1 Inventory of waste disposed 2.2 Projections of waste to be disposed 2.3 Per capita waste reduction goals	Page 11
Section 3 Waste Reduction Element 3.1 Inventory of waste reduction programs 3.2 Disaster debris management 3.3 Assessment of waste reduction programs 3.4 Needs and goals	Page 17
Section 4 Collection Element 4.1 Inventory of collection 4.2 Assessment of collection programs 4.3 Inventory of illegal dumping/littering 4.4 Assessment of programs to address illegal dumping	Page 25
Section 5 Disposal Element 5.1 Inventory of solid waste disposal facilities 5.2 Assessment of disposal 5.3 Needs and goals	Page 30
Section 6 Land Limitation Element 6.1 Inventory land areas 6.2 Local procedures for siting solid waste facilities 6.3 Assessment of land limitation 6.4 Needs and goals	Page 34
Section 7 Education and Public Involvement Element 7.1 Inventory of existing public education/involvement progra 7.2 Assessment of environmental education initiatives 7.3 Needs and goals	Page 43
Section 8 Implementation Strategy 8.1 Summary of needs and goals 8.2 implementation strategy, short-term work program	Page 46

Solid Waste Management Plan 2008-2018

Section 9 Appendix Page 48

Appendix A: Bulloch County resolutions
Appendix B: City of Statesboro resolutions
Appendix C: City of Brooklet resolutions
Appendix D: City of Portal resolutions
Appendix E: City of Register resolutions
Appendix F: Public Hearing Notices

Appendix G: Broadhurst Landfill Capacity Assurance Letter

Appendix H: Clean Community Ordinance

Appendix I: Copies of approval letters from state reviewing agencies

Section 1 Introduction

1.1 Define Planning Area

This multi-jurisdictional plan covers unincorporated Bulloch County as well as the Cities of Statesboro, Brooklet, Portal and Register. See Appendix for resolutions from the County and each municipality adopting this Solid Waste Management Plan.

1.2 Identify Person Responsible for the Plan

The person responsible for the updated Bulloch County-Statesboro-Brooklet-Portal-Register Solid Waste Management Plan is:

Brooke Carney Director, Keep Bulloch Beautiful 17315 Highway 301 North Statesboro, GA 30458 T: (912) 764-6147

F: (912) 764-8768

E: brooke@keepbullochbeautiful.org

Any questions regarding the plan or requests for additional information can be directed to Mrs. Carney.

1.3 Overview of the Area Covered in the Plan

1.3.1 Planning Area

Bulloch County is located in southeast Georgia in the Ogeechee River watershed. It is located approximately 200 miles to the southeast of Atlanta at Latitude: 322500N and Longitude: 0814502W.

The total area included in this plan covers approximately 682 square miles. The relative location of Bulloch County as well as the municipalities located within the county is shown on the locality map below.

Solid Waste Management Plan 2008-2018




Figure 1.1-A Relative location of Bulloch County in state


Figure 1.1-B Location of municipalities in County

1.3.2 Topographic Information

Bulloch County is in the eastern part of the Coastal Plain region. The county is divided among two districts within the region: the Vidalia Upland District and the Barrier Island Sequence district. The topography of the county changes with the transition from one district to the other, with more rolling hills and higher elevations in the northwestern half of the county and very level land and lower elevations in the southeastern half. Bulloch County has few areas with steep enough slopes to limit development. The highest elevation in the county is less than 350 feet above sea level, which is located in the Portal area, and the lowest elevations reach 50 to 100 feet above sea level in the southern part of the county.

The majority of the county's watershed is associated with the Ogeechee River, which makes up the eastern border of the county. Numerous documented wetlands and several groundwater recharge areas are located throughout the county, and the majority of these are located in the southern half of the county. The total area of 100 year floodplain for the county is estimated to be 250,000 acres.

Figure 1.2: Bulloch County Topography



1.3.3 Population

The table below represents population projections for each entity covered by this plan over a ten year period. Baseline population figures were taken from the most recent U.S. census data available. Projections for future population in 2010 and 2015 were taken from a study conducted for the coastal Georgia Regional Development center by Georgia Tech titled *Georgia Coast 2030*. All other figures are estimations based on projected growth.

Table 1.1 Population Projections

Jurisdiction	2006 (base year)	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018
Statesboro	25583	26329	27075	27821	28127	28434	28740	29047	29349	29665	29982	30297
Brooklet	1222	1269	1316	1364	1379	1394	1409	1424	1439	1455	1469	1486
Portal	595	640	685	732	740	748	756	764	772	780	788	798
Register	163	175	187	201	204	206	208	210	212	214	216	218
Unincorporated Bulloch County	35644	36598	37552	38500	38922	39344	39767	40189	40616	41054	41493	41929
TOTAL	63207	65011	66815	68618	69372	70126	70880	71634	72388	73168	73948	74728

Source: Georgia Coast 2030, Georgia Tech

1.3.3.1 Seasonal Population Variation

The population of Bulloch County varies greatly depending on the time of year. Georgia Southern University is located in Statesboro and has a student population of approximately 17,000. The student population is significantly lower during summer months. In addition, many faculty members conduct research out of town. Furthermore, summer population is lower as a result of families vacationing out of the area.

The following information was provided by the Statesboro Convention and Visitor's Bureau. In our region in 2006, 31% of our domestic travelers traveled in the first quarter, 20% in the second quarter, 20% in the third quarter, and 30% in the fourth quarter. In our region, 56% are overnight guests and 44% are daytrip visitors. In our region, 70% of travelers are in-state travelers and 30% are out-of state travelers Of the in-state tourists visiting Bulloch County, 58% came in the first quarter, 60% second quarter, 64% third quarter, and 63% fourth quarter. For out of state tourists, 42% traveled during the first quarter, 40% during the second quarter, 36% during the third quarter, and 37% during the fourth quarter. Of travelers visiting the area, 72% travel by automobile including RVs, campers and cars; 3% by air, and 26% by other means. Bulloch County's primary visitor is a domestic traveler with an average age of 46. Most travelers are from 2-3 person households and most have no children. Other groups that frequently travel to Bulloch County include student travel groups, sports tournament groups and "snowbirds" – U.S. Highway 301 travelers.

1.3.3.2 Number of Households

Table 1.2 Number of Households in Planning Area

Table 1.2 Rulliper of Householde III I letting 7 u.o.	2005
Jurisdiction	2005
Statesboro	9525
Brooklet	432
Portal	228
Register and Unincorporated Bulloch County	12909
TOTAL	23094

Source: Georgia Planning.com

1.3.4 Economic Activity

1.3.4.1 By SIC Code

Table 1.3 Economic Activity by SIC Code

Economi	c Activity by Si	IC Code
SIC Code	Jurisdiction	Number of Businesses 2007
2013	Statesboro	1
2035	Statesboro	1
2068	Statesboro	1
2086	Statesboro	1
2087	Statesboro	1
2099	Statesboro	1
2321	Portal	1
2331	Portal	1
2337	Portal	1
2339	Portal	1
2395	Statesboro	2
2396	Statesboro	3
2421	Brooklet	1
2421	Statesboro	2
2431	Statesboro	1
2434	Brooklet	1
2434	Statesboro	1
2439	Brooklet	1
2449	Statesboro	1
2491	Statesboro	1

2499	Statesboro	1
2511	Statesboro	3
2541	Brooklet	1
2653	Statesboro	1
2711	Statesboro	2
2741	Statesboro	1
2752	Statesboro	1
2759	Statesboro	6
2789	Statesboro	1
2791	Statesboro	3
2875	Statesboro	3
2951	Statesboro	1
3089	Brooklet	2
3089	Statesboro	1
3231	Statesboro	1
3272	Brooklet	1
3272	Statesboro	1
3273	Brooklet	1
3273	Statesboro	2
3312	Statesboro	1
3341	Statesboro	3
3441	Brooklet	1
3444	Statesboro	1
3446	Statesboro	1
3451	Statesboro	1
3462	Statesboro	1
3491	Statesboro	1
3499	Statesboro	4
3519	Statesboro	1
3523	Statesboro	1
3541	Statesboro	1
3544	Statesboro	2
3599	Statesboro	9
3822	Statesboro	1
3823	Statesboro	1
3825	Brooklet	1
3825	Statesboro	1
3993	Statesboro	7
3999	Statesboro	1

Source: GeorgiaFacts.net

1.3.4.2 Number of Employees by Sector

Table 1.4 Number of Employees by Sector in Planning Area

Sector	2006
Goods Producing	
Agriculture, Forestry, and Fishing	278
Construction	1503
Manufacturing	2159
Service producing	
Wholesale Trade	515
Retail Trade	3365
Transportation, warehousing and Utilities	1026
Services	8037
Other	27
Government	
Federal	139
State	3472
Local	2412
Total for all industries	22933

Source: Georgia Department of Labor

Section 2 Waste Disposal Stream Analysis

2.1 Inventory of Waste Disposed

All waste disposed in Bulloch County, including that disposed of by each jurisdiction and that which is collected by private haulers, goes to the Statesboro-Bulloch Transfer Station and Recycling Facility (the Transfer Station), which is owned jointly by the City of Statesboro and Bulloch County and operated exclusively by the City. At the Transfer Station, waste is separated into various areas, including MSW transfer station, inert site, yard waste, scrap tires, and recycling. The chart below outlines the waste disposed of at the Transfer Station, excluding recyclable commodities (tires, metal, paper, etc).

The annual report for Transfer Station FY 2007 (July 1, 2006 – June 30, 2007) was used to develop the chart below. Materials being transferred into an MSW landfill are noted as such. Percentages for MSW waste generated by residential, commercial, and industrial sectors were based on the State of Georgia's Solid Waste Management Plan. The State's Plan notes that, on average, 39.1% of MSW waste is residential, 27.5% is commercial, 14% is industrial, 12.3% is construction and demolition (included under "C&D"), and 7.1% is bio-sludge from wastewater treatment plants (included under "other").

Table 2.1 Waste Disposed by Sector: FY 2007

	MSW La	ndfill = 47,526.	37 tons					
Jurisdiction	Residential	Commercial	Industrial	C&D	Inert	Yard Trimmings	Other	TOTAL
Bulloch						J		
County	18583	13070	6654	27911	7507	7683	3484	84891

Source: Statesboro-Bulloch County transfer Station and Recycling Facility records, State of Georgia Solid Waste management Plan

Because the Transfer Station annual report is categorized differently than the above chart, an explanation of how the Transfer Station report categories were converted into those used in Table 2.1 is below.

	Conversions defined						
2008 SW Plan category	Transfer Station report category						
MSW	household, bulk, mixed, gov waste, dot waste, bull trans						
C&D	demolition, shingles, sweepings, 12.3% of total MSW						
Inert	inert, cover dirt						
Other	animal waste, road kill, bio-sludge (7.1% of MSW)						

2.1.1 Waste Characterization

Data collected by the State of Georgia for the Statewide Waste Characterization Study was used to develop the table below. The data represents waste grouped by material in the Coastal Georgia region. Field sampling was conducted at Superior Landfill in Savannah, Georgia.

The statewide study showed that in the coastal area of Georgia, approximately 39% of the waste stream is paper. Of the paper disposed, 31.4% is recyclable. Plastic makes up 16% of the waste stream, and almost half of the plastic disposed of in landfills is film plastic. Food waste makes up 11.1% of waste disposed. Other amounts can be seen in Table 2.2 below. Based on the data collected in the statewide study, approximately 42.8% of waste disposed could be diverted by recycling programs already in place in Bulloch County.

Table 2.2 Waste Composition Detail for Coastal Georgia by weight (annual)

Group	Material	Tons Disposed	Average Percent
Paper	Newspaper	20,291	4.50%
T 10 100	Corrugated cardboard	67,943	15.00%
	Office	15,550	3.40%
	Magazine/glossy	10,498	2.30%
	paperboard	15,697	3.50%
	mixed	12,438	2.70%
	other (non-recyclable)	34,889	7.70%
	Total Paper	177,306	39.10%
Plastic	#1 PET bottles	5,799	1.30%
The state of the s	#2 HDPE bottles	4,618	1.00%
	#3-#7 bottles	964	0.20%
	expanded polystyrene	6,294	1.40%
	film plastic	35,798	7.90%
	other rigid plastic	18,925	4.20%
	Total Plastic	72,398	16.00%
Glass	clear	7,127	1.60%
	green	2,424	0.50%
	amber	6,001	1.30%
	other	319	0.10%
	Total Glass	15,781	3.50%
Metal	steel cans	4,378	1.00%
	aluminum cans	3,688	0.80%
	other ferrous	7,277	1.60%
	other non-ferrous	4,371	1.00%
	Total Metal	19,713	4.30%

Solid Waste Management Plan 2008-2018

Organics	yard waste	12,555	2.80%
	wood (non C&D)	9,872	2.20%
	food waste	50,582	11.10%
	textiles	19,307	4.20%
	diapers	11,856	2.60%
	fines	10,005	2.20%
	other organics	13,907	3.10%
	Total Organic	128,084	28.20%
C&D	drywall	963	0.20%
	wood	19,960	4.40%
	inerts	1,117	0.20%
	carpet	3,119	0.70%
	other C&D	4,102	0.90%
	Total C&D	29,292	6.40%
Inorganics	televisions	0	0.00%
	computers	3,732	0.80%
	other electronics	4,839	1.10%
	tires	0	0.00%
	HHW	1,129	0.20%
	other inorganics	2,096	0.50%
	Total Inorganics	11,797	2.60%
	TOTAL	454,429	100.00%

Source: Georgia Statewide Waste Characterization Study

2.1.2 Unique Conditions and/or Seasonal Variations

Georgia Southern University is located in Statesboro, and students move in and out each May and December. These two events cause significant increases in the amount of waste weighed in at the Transfer Station. Another seasonal trend is dependent on construction activity. The months of May, June, and July are the busiest months for the construction industry and noticeably higher amounts of waste are generated during this time. The months of October, November and December are typically slower for the construction industry, and weight reports reflect this trend.




Figure 2.1 Weight into Transfer Station by month during FY 2007 (in tons)

Source: Transfer Station weight reports and interview with Mickey Dickey, Landfill Supervisor (12/13/07)

2.1.3 Waste Generating Disasters

Although difficult to predict, natural disasters, such as tornadoes, flooding, hurricanes, wild fires, and ice storms, have the potential to tremendously increase the amount of waste generated in Bulloch County. The sections of this Solid Waste Management Plan on collection and disposal outline the approach that the County and all municipalities within the county would take to deal with waste resulting from disasters.

2.2 Projections of Waste to be Disposed

In order to project the amount to be disposed over the timeframe of this plan, the current population was compared to the total amount disposed to get a per capita waste disposal rate. The figure (1.34 tons/person/year) was then increased each year by .02 tons, which is the rate, set by the State of Georgia, at which waste disposed per capita has increased each year since 1994. Waste reduction programs or goals have not been factored into this per capita waste disposal rate. The projected daily waste has also been included to assist Statesboro-Bulloch County Transfer Station operators with plans for expected daily loads coming into the transfer Station.

Table 2.3 Projected Waste to be Disposed

All Jurisdictions	2007	2008	2009	2010	2011	2012
TOTAL TONS	84,890.77	88,414.96	92,204.70	96,065.20	98,508.24	100,981.44
population	63,207	65,011	66,815	68,618	69,372	70,126
amount per capita (tons)	1.34	1.36	1.38	1.4	1.42	1.44
total tons per day*	232.58	242.23	252.62	263.19	269.89	276.66

^{*}excludes recyclables, 365-day year

All Jurisdictions	2013	2014	2015	2016	2017	2018
TOTAL TONS	103,484.80	106,018.32	108,582.00	111,215.36	113,879.92	116,575.68
population	70,880	71,634	72,388	73,168	73,948	74,728
amount per capita (tons)	1.46	1.48	1.5	1.52	1.54	1.56
total tons per day*	283.52	290.46	297.48	304.7	312	319.39

^{*}excludes recyclables, 365-day year

Source: Transfer Station reports, Georgia Coast 2030, Georgia Solid Waste Management Plan

2.3 Per Capita MSW Disposal Reduction Goal

The table below shows the base year as being the year of Bulloch County's original solid waste plan. Because the per capita waste rate has increased significantly between the base year and the current year, current year figures are used to calculate the 25% waste reduction goal over the next ten years. In order to reach 25% reduction goal by 2018 per capita waste will need to be reduced by .032 tons per year. Per capita waste in 2008 is projected to be 1.36 tons. Meeting waste reduction goals will lower per capita waste .032 tons in 2008 to 1.328 tons and an additional .032 tons each year through 2018.

Table 2.4 Per capita Waste reduction Goals and Projections

All Jurisdictions	base year (1993)	2007	2008	2009	2010	2011	2012
TOTAL TONS	45,233	84,890.77	88,414.96	92,204.70	96,065.20	98,508.24	100,981.44
population	44,705	63,207	65,011	66,815	68,618	69,372	70,126
amount per capita (tons)	1.01	1.34	1.36	1.38	1.4	1.42	1.44
Per capita reduction goal disposed from base year	N/A	N/A	1.328	1.296	1.264	1.232	1.2

All Jurisdictions	2013	2014	2015	2016	2017	2018
TOTAL TONS	103,484.80	106,018.32	108,582.00	111,215.36	113,879.92	116,575.68
population	70,880	71,634	72,388	73,168	73,948	74,728
amount per capita (tons)	1.46	1.48	1.5	1.52	1.54	1.56
Per capita reduction goal disposed from base year	1.168	1.136	1.104	1.072	1.04	1.006

Source: U.S. Census, Georgia coast 2030, Georgia Solid Waste Management Plan, original Bulloch County Solid waste Management Plan (1993)

Section 3 Waste Reduction Element

Waste reduction efforts and programs listed in this section include unincorporated Bulloch County, City of Statesboro, City of Brooklet, City of Portal and City of Register unless otherwise noted.

3.1 Inventory of Waste Reduction Programs

Waste reduction is primarily offered through the County's drop-off recycling centers as well as its corrugated cardboard pick-up service. In addition, Keep Bulloch Beautiful coordinates recycling programs at all public schools, Ogeechee Technical College and during special collection events. Other waste reduction programs include recycling at Georgia Southern University, Viracon, Wal-mart Super Center and Distribution Center, Briggs and Stratton, Lowes and other industrial and institutional entities. The City of Statesboro offers curbside pick-up for white goods and yard waste. All recyclables and items requiring special handling are processed at the Statesboro-Bulloch County Transfer Station and Recycling Facility and sold to scrap metal recyclers.

Waste reduction is primarily encouraged by Keep Bulloch Beautiful through a variety of education, volunteer participation, and public awareness programs and events. Other efforts to promote waste reduction include those made internally at the above mentioned institutions and industrial entities.

3.1.1 Source Reduction

Source reduction is promoted by Keep Bulloch Beautiful through education and public awareness efforts. Audiences reached by these educational efforts include residences and small businesses in the county. Additionally, several commercial and industrial entities have existing waste reduction programs, such as paperless communications and electronic filing systems as a way of reducing unnecessary costs. Wal-mart Distribution Center also has a polystyrene reducer to decrease the amount of waste being generated from their business. Also, several local lawn and tree businesses mulch organic waste in an effort to reduce waste and avoid charges at the Transfer Station.

3.1.2 Recycling

Table 3.1 Existing Recycling Programs in Bulloch County*

Type of Program	Population served	operated by	materials accepted	tons diverted (FY 2007)
Drop-off Center	Accessible to 23094 households	Bulloch County	corrugated cardboard mixed paper newsprint #1 PET plastic #2 HDPE plastic aluminum steel scrap metal Glass, mixed	1668 100.4 117 24.28 36.42 7.12 0 924 159.8
School recycling program		KBB/Bulloch County	mixed paper #2 HDPE	32 8.4
Collection service		Bulloch County	cardboard	N/A
Business recycling program		КВВ	mixed paper #1 PET plastic aluminum	N/A N/A
Donation Centers	23094 households	Goodwill Industries Habitat for Humanity	clothing household items household items	256 N/A
Buy Back Center		Ink Jet Office Depot Stubbs Metal	ink cartridges ink cartridges metal (list types) auto parts?	N/A N/A N/A N/A
Grocery Bag		Wal-Mart Bi-Lo	#2 and #4 film plastic #2 and #4 film plastic	N/A N/A
Curbside pick-up	Information not available	Thomas Disposal	PET, HDPE, glass, cans, newsprint	not available

^{*}excludes programs for materials requiring special handling (electronics, HHW, etc)

All end users, or recipients of, material recycled in Bulloch County are located outside the county. A table showing end users currently being used is below. Does Stubbs (or anyone else) melt and resell metal here in the county?

Table 3.2 Businesses that Accept Materials from Bulloch County

Name	Location	Geographic Area	Sector	Materials Accepted
KW Plastics	Troy, AL	United States	residential	#2 HDPE plastics
Smurfit	Augusta, GA	United States	residential	OCC, aluminum cans
Strategic Materials	Atlanta, GA	United States	residential, commercial	glass
Ft James	Rincon, GA	United States	residential, commercial	baled ONP, Mixed ONP/Magizines, Office, baled OCC
Mohawk	Dalton, GA	United States	residential	#1 PET plastic
Gann Car Crushing	Pembroke,GA	United States	residential, commercial	scrap metal, baled tin
Williams Brothers Trucking	Savannah, GA	Georgia	residential, commercial	yard waste

Source: Bulloch County Environmental Management

3.1.2.2 Recycling Facilities

Other than the recycling processing facility owned and operated by Bulloch County, none exist within the county.

3.1.3 Yard Trimming Programs and Facilities

Municipal curbside pick-up service is offered by the City of Statesboro to residents within the city limits. Each of the 16 recycling centers located throughout the county offers free drop-off sites for residential yard waste. Private landscaping and tree businesses, as well as residents with larger loads, must dispose of yard waste at the Transfer Station for a fee of \$12.96 per ton. Yard waste collected through each of the aforementioned programs is ground at the transfer Station by a private contractor and then sold to various markets, including the waste-to-energy facility in Savannah.

An inert site is also located at the Statesboro-Bulloch County Transfer Station and Recycling Facility. Home composting is encouraged by programs conducted by Keep Bulloch Beautiful, Georgia Southern Botanical Garden and other local organizations.

Solid Waste Management Plan 2008-2018

Table 3.3 Yard Waste Programs

Program	Owner/ Operator	jurisdictions served	sector served	materials accepted	quantity	program maximum capacity	final disposition
Compost education program	Keep Bulloch Beautiful	All	R	N/A	N/A	N/A	residential compost
Compost education program	Georgia Southern Botanical Garden	All	R	N/A	N/A	N/A	residential compost
GSU Physical Plant, Grounds Dept.	Georgia Southern University	Statesboro	1	leaves, wood			
private tree, landscaping entities	multiple	All	I, C, R	Yard waste			Private businesses
Municipal curbside yard trimmings	City of Statesboro	Statesboro	R	leaves, wood		N/A	i i i i i i i i i i i i i i i i i i i
Municipal drop- off yard trimmings	Bulloch County	All	R	leaves,		N/A	Mulched, used for waste-to- energy facility (Sav)

3.1.4 Items Requiring Special Handling

The table below describes the methods used for disposing of various items which require special handling in Bulloch County. Handling for all jurisdictions is included on this table.

Table 3.4 Items requiring Special Handling

Material	Target Sector(s)	Management Strategy	Final Disposition of materials(s)
Electronics	R, I, C	permanent drop-off site, 2 events held annually	Dismantled by private recycler, parts resold
White Goods	R	drop-off sites located at recycling centers throughout county	Sold with scrap
White Goods	R	curbside pick-up service in Statesboro	Sold with scrap metal
tires	R	drop-off sites located at recycling centers throughout county, no charge	MTR of Georgia
tires	C,1	Drop-off at main recycling facility, \$ per ton	MTR of Georgia
ead acid patteries		Handled by private sector entities	Stubbs Wrecking Yard, Advanced Auto Parts
HW	R, I, C	no special event held in recent years	

R = Residential, I = Institutional, C = Commercial

3.2 Disaster Debris Management - Waste Reduction Strategy

In the event of a natural disaster or emergency situation that interrupted the Cities' and County's normal operations for providing waste reduction and recycling services, the County has several options. The County can negotiate with private haulers and/or recyclers in the area to accept recyclables from all jurisdictions within the county. Negotiations can include the City of Statesboro and Bulloch County sharing the processing cost of any recyclables delivered by residents and/or commercial establishments. Another option would be to temporarily store recyclable materials in publicly owned facilities until normal operations can be resumed.

3.3 Assessment of Waste Reduction Programs

Bulloch County began collecting MSW at unmanned dumpster sites in 1970. This program existed until 1994 at which time there were 435 dumpsters at 75 different locations. In 1994 Bulloch County began implementing its collection centers, each one eliminating 25-30 dumpsters. Bulloch County has had a residential drop-off recycling program since 1994. In addition, other components of the county's recycling program, such as cardboard and curbside yard waste pick up (City of Statesboro only), have all been in place for several years. The county's recycling program has experienced a steady increase in participation and amount of material received since the program was established. In response to the decreasing proportion of material being recycled, Keep Bulloch Beautiful, in conjunction with the County, has recently established several new components of the county recycling program. These include an unstaffed drop-off recycling center at Wal-mart Super Center in Statesboro, a voluntary business recycling program, paper recycling at Ogeechee Technical College, and system-wide mandatory public school recycling program.

Plans are in place to expand the existing recycling processing facility. In addition, a grant recently received from the State of Georgia has established Bulloch County as a regional recycling hub and provided supplemental funding to support the expanded recycling program. Plans to expand the existing program include a voluntary curbside recycling program in Statesboro, processing equipment, storage containers, vehicles, assistance to neighboring communities for recycling, and a more efficient means of receiving and processing materials are all in the plans to improve the county's recycling program. In addition, drop-off recycling centers are planned for downtown Brooklet, the Brooklet-Leefield area, Union Church Rd. area, and the Bay District area (Arcola Rd.-Hwy 46), which will replace several sets of roadside dumpsters. Also, some of the existing collection centers may be changed from 5 day to 7 day schedules. Keep Bulloch Beautiful has also recently received an Away from Home recycling grant, which will allow more recycling to take place at special events throughout the county.

Bulloch County has an adequate program in place to successfully meet the waste reduction goals set by the state. Methods to increase participation in the established

and planned programs will be the determining factor in meeting the waste reduction goals adopted by the Georgia State Legislature. See figure below.

Commodity	Actual 2004 Lbs/person	Projected 2012 Lbs/person	Projected % 2012	Projected 2017 Lbs/person	Projected % 2017
Glass	0.153	0.14	8%	0.14	8%
Paper	1.181	1	15%	0.85	28%
Metal	0.228	0.198	13%	0.186	18%
Plastic	0.663	0.56	16%	0.53	20%
Total	2.23	1.99	11%	1.71	23%

Special attention should be paid to paper recycling, as it comprises approximately 40% of the waste stream. Also, working with private haulers that operate outside the City of Statesboro to offer recycling pick-up service will play an important role in reducing waste. Continuation of existing educational programs on source reduction will also to be an important part of reducing waste.

Currently, there is no established plan for offering proper disposal and recycling of Household Hazardous Waste. Plans to hold events on an annual basis need to be established.

Organic waste, and food waste in particular, comprises a significant amount of the waste stream (28%). Attention should be given to improving the existing educational and municipal composting programs.

Currently, no special recycling or reuse programs are in place for the Georgia Southern student move-outs that happen twice annually. Establishing mobile recycling centers or educational programs targeted at these two events are needed to reduce the seasonal increase in waste created by them.

3.4 Needs and Goals

<u>Goal:</u> Increase participation in drop-off recycle center program by 25%. (Measure in tons recycled annually.)

Strategy:

- Establish more drop-off centers to be located in places convenient to growing population.
- Maintain extensive hours of operation currently in use.
- Increase educational efforts targeted at community residents.

Solid Waste Management Plan 2008-2018

Improve signage at recycling centers to assist with source separation.

Goal: establish voluntary curbside recycling program in City of Statesboro Strategy:

- Use funds from state grants as well as locally provided funds, supply curbside collection containers, weekly service, and adequate processing capabilities to residents inside the city limits of Statesboro.
- Coordinate educational efforts through Keep Bulloch Beautiful.

Goal: Increase participation in school recycling program. Strategy:

- Use recently purchased vehicle to make collection more efficient, thus, eliminating chronic overflow problem at schools and increasing use of collection containers.
- Continue educational programs.
- Continue award program.

Goal: Increase participation in business recycling program.

Strategy:

- Continue educational efforts.
- Continue to offer "start-up kits" at discounted price to local businesses.
- Continue to offer guidance and in-kind consulting services to businesses in community on reducing waste.
- Target large businesses in community and offer customized recycling services.
- Continue encouraging those businesses already participating in voluntary program.

Goal: Reduce waste created by Georgia Southern student move-out each May and December.

Strategy:

- Establish educational program targeted at GSU students.
- Offer mobile recycling centers or other service to student housing areas.
- Work with Georgia Southern University administration to establish programs aimed at reducing move out waste.
- · Partner with Goodwill, Habitat for Humanity, or other similar entity to accept unwanted household items.

Goal: Offer means of disposal for household hazardous waste. Strategy:

Partner with private disposal company and host annual Household Hazardous Waste (HHW) collection event in conjunction with Great American Cleanup events.

Goal: Reduce amount of organic waste going into landfill. Strategy:

Solid Waste Management Plan 2008-2018

- Improve and increase educational programming about composting.
- Address feasibility of operating municipal composting program.

<u>Goal:</u> Reduce amount being disposed in residential trash cans. <u>Strategy:</u>

- Offer voluntary curbside recycling program inside Statesboro city limits (to be operated by Bulloch County).
- Encourage private haulers to offer curbside recycling service.

Section 4 Collection Element

As in each section of this Solid Waste Management Plan, the cities of Statesboro, Register, Brooklet and Portal as well as unincorporated Bulloch County, unless otherwise noted, are included in collection management plans listed in this section.

4.1 Inventory of Collection

Table 4.1 below describes the haulers operating in the county and table 4.2 describes the various solid waste collection methods used in Bulloch County.

Table 4.1 Haulers Operating in Bulloch County

	o operating in a			
Hauler Name	Hauler Address	Sector Served	Jurisdiction(s)	Arrangement
Southern Disposal Service	Trauler Address	C, I, R		independent contract with generator
Power Waste Systems, INC	159 Little Canoochee Creek Rd Twin City, GA	C, I, R		independent contract with generator
Bulloch County Solid Waste	17315 Hwy 301 N Statesboro	C, I, R	Portal, Brooklet, Register, unincorporated	offered by local government
Sullivan Environmental Services	PO Box 370 Twin City, GA	C, I, R	unincorporated Bulloch County	independent contract with generator
Thomas Disposal Service	87 Pine Needle Ln Statesboro	C, I, R	unincorporated Bulloch County	independent contract with generator
Live Oak Environmental	4008 Denton Loop Statesboro, GA	C, I, R	unincorporated Bulloch County	independent contract with generator
City of Portal	27209 Hwy 80 Portal, GA	R	Portal	offered by local government
City of Brooklet	104 Church St Brooklet, GA	R	Brooklet	offered by local government
City of Statesboro	PO Box 348 Statesboro, GA	R, C	Statesboro	offered by local government

Source: phone interviews with haulers (12-17-07)

Table 4.2 Inventory of Collection Programs in Bulloch County

Туре	Collector	Program Description	Jùrisdictions ' Served	Sectors Served	# of households/businesses served, if available	contractual arrangements
	Southern Disposal Service	weekly garbage	unincorporated Bulloch County	residential		independent contract with generator
	Thomas Disposal	weekly garbage, twice monthly recycling	unincorporated Bulloch County	residential		independent contract with generator
curbside collection	Live Oak Environmental	weekly garbage	unincorporated Bulloch County	residential		independent contract with generator
	City of Statesboro	weekly garbage collection, monthly yard waste and bulky items	Statesboro Inc.	residential		city ordinance
	City of Brooklet	weekly garbage	Brooklet Inc.	residential		city ordinance
195., 197.,	City of Portal	weekly garbage	Portal Inc.	residential		city ordinance
	Southern Disposal Service	1-5 times weekly as needed	all of Bulloch County	commercial, industrial, construction		independent contract with generator
compactor	Sullivan Environmental Services	1-5 times weekly as needed	all of Bulloch County	commercial, industrial, construction		independent contract with generator
and roll-off	Power Waste Systems, Inc	1-5 times weekly as needed	all of Bulloch County	commercial, industrial, construction		independent contract with generator
	Bulloch County Solid Waste	1-5 times weekly as needed	all of Bulloch County	commercial, industrial, construction		independent contract with generator
commercial dumpster	Southern Disposal Service	1-5 times weekly as needed	unincorporated Bulloch County	commercial, industrial, construction		independent contract with generator

	City of Statesboro	1-5 times weekly as needed	Statesboro Inc.	commercial	city ordinance
	Sullivan Environmental Services	1-5 times weekly as needed	unincorporated Bulloch County	commercial, industrial, construction	independent contract with generator
staffed drop-off sites	Bulloch County Solid Waste	serviced as needed	throughout Bulloch County	residential	operated by local government
unstaffed drop-off sites	Bulloch County Solid Waste	30 unstaffed dumpster sites located in rural areas of county	throughout Bulloch County	residential	operated by local government
collection service	New River Construction, LLC	construction waste collection	throughout Bulloch County	construction	independent contract with generator
collection service	Georgia Southern University	campus waste collection	GSU campus only	institutional	operated by University
collection service	James Sturgeoun Collection	residential, commercial collection	throughout Bulloch County	residential	independent contract with generator
collection service	Johnson's Sanitation Service, Inc.	residential, commercial collection	unincorporated Bulloch County	residential, commercial	independent contract with generator
collection service	C&D Services	commercial, industrial	unincorporated Bulloch County	construction and demolition collection	independent contract with generator

Sources: Phone interviews with private companies, interviews with each jurisdiction, Georgia Environmental Protection Division

4.1.2 Contingency Strategy

Because both public and private collection services are offered, it is unlikely that all collection services would be disabled at once. In the event that one or more collection services are interrupted, jurisdictions in Bulloch County will partner to assist with the jurisdiction in need. Several private haulers are also available for contract work in the event that one or more jurisdictions' collection service is interrupted.

In the event that no government-owned vehicles could collect garbage, one of the private haulers with locations outside the county would likely be used to temporarily provide collection service. In addition, Bulloch County operates 16 staffed drop-off sites

and 30 unstaffed drop-off sites that could serve as the only temporary means of waste collection if needed.

If any of the above mentioned contingency plans are needed, it would take 24-26 hours to put one or more of them in place.

4.1.3 Disaster Debris Management -- Collection Strategy

City of Statesboro has five grapple trucks and Bulloch County has one grapple truck. In addition, the City of Statesboro and Bulloch County have a combined fleet of ten back hoes and front end loaders. All of the equipment would be used to collect waste generated from a disaster. Where feasible, yard waste would be segregated from bulk waste using grapple trucks. Statesboro and Bulloch County public works equipment would also be used to assist with waste collection and debris removal. If needed, the County's roll-off rental service would temporarily be suspended to allow containers to be used for debris removal. Recycling centers would remain open, and wherever feasible recyclable materials would be segregated into piles using public works equipment and then loaded into county roll-off trucks.

4.2 Assessment of Collection Programs

Each jurisdiction in Bulloch County offers adequate collection services for garbage, bulky items, yard waste and recycling based on the current and projected population. The City of Statesboro is lacking a curbside recycling program, but plans for establishing such a program are in place. Several private haulers also provide garbage collection service to all sectors of the community, and many have either recently begun or are planning to offer curbside recycling services for residential areas.

Because of the large geographic area of Bulloch County and the many areas still considered to be rural, staffed recycling centers in every neighborhood are not financially feasible. Unstaffed dumpsters are located in rural areas and are routinely abused. Unmanned dumpster sites are not adequate for long term solid waste planning. As the need for solid waste disposal sites will only increase with the growing population, plans to improve the unstaffed dumpster sites need to be established, including fences, surveillance cameras, etc.

4.3 Inventory of Illegal Dumping/Littering

Despite ongoing efforts against it, illegal dumping and littering remains a problem in Bulloch County. Several unmanned dumpster sites are chronically abused, including the Arcola/Hwy 46 site and the Groveland/Old Groveland Road site. In addition, many places along dirt and paved roads, especially in the more rural areas of the county, have long been established as recurring illegal dump sites. The presence of litter has decreased in many areas of the county but problem areas still exist.

Bulloch County code enforcement handles the majority of the enforcement duties in the areas outside Statesboro city limits. In addition, officers with the Statesboro Police Department, Bulloch County Sheriff's Department, DNR Bulloch County unit, Statesboro City Marshal, and Georgia State Patrol Post 45 have all completed the Litter Enforcement Training Program, a component of the Governor Perdue's Litter Initiative.

4.4 Assessment of Programs to Address Illegal Disposal/Dumping

Several programs, including those that focus on education, eradication, and enforcement, currently address illegal dumping and littering issues. As the population grows, more resources will need to be dedicated to this in order to maintain and improve the current level of litter and illegal dumping. Improvements to the existing programs should include one or more additional litter work details, one or more additional code enforcement officers, and increased resources for public education.

4.5 Needs and Goals

Goal: Provide residents living in all areas of the county with accessible and convenient means of properly disposing of trash and recyclables. The County and each municipality lying within the county must ensure proper collection services, whether public or private, are in place for trash and recyclables collection.

Strategy:

- Maintain citywide trash collection service in Statesboro
- Maintain recycling and trash drop-off centers throughout county (add additional centers as needed by population increase
- Continue to accept household trash and recyclables from private haulers operating outside Statesboro
- Encourage private haulers to offer curbside recycling programs using County's new single-stream processing facility

Section 5 Disposal Element

As in each section of this Solid Waste Management Plan, the cities of Statesboro, Register, Brooklet and Portal as well as unincorporated Bulloch County are included in the disposal management plans listed in this section.

5.1 Inventory of Solid Waste Disposal Facilities

All MSW collected within Bulloch County is required to be delivered to a permitted solid waste disposal facility operating in compliance with applicable federal, state, and local laws. All MSW currently received at the Statesboro-Bulloch Transfer Station is transported to Boradhurst Landfill. Inert waste is disposed of on site at the Inert Landfill located on the same property as the closed Statesboro Bulloch Landfill and the Statesboro-Bulloch County Transfer Station.

Disposal facilities located in Bulloch County

Facility Name*	Physical Address	Owner/ Operator	Facility Type**	Maximum Capacity (TPD)	Years Expected to Reach capacity
Statesboro-Bulloch Inert Site	999 Lakeview Rd Statesboro, GA		Inert	22 tons/day	12/31/2008
Statesboro Bulloch Landfill	999 Lakeview Rd Statesboro, GA	City of Statesboro	MSW	Closed in 1996	N/A
Broadhurst Environmental Landfill	Screven, GA 31560	Boradhurst	MSW		12 yrs remaining capacity
GREGORY BRIDGE COSR67 INERT LF	SR67 NEAR BRYAN COUNTY LINE		Inert		
NEAL TUCKER OLD HARDY PLACE INERT LF	OLD HARDY PLACE		Inert		Meserchiada La companya da santa
SOUTHEASTERN UTILITIES CONTRACTORS, INC.	REED AND RAYMOND STREETS IN WHITESVILLE S/D		Inert		
RONNIE R. HILL, SR. INERT LANDFILL	STOCKYARD ROAD		Inert		
SAM O. JOHNSON INERT LANDFILL	7532 HWY. 301 S.		Inert		
SOUTHEASTERN UTILITIES CONTRACTORS, INC.	REED ST AND RAYMOND ST IN WHITERVILLE SUB NE OF STATESBORO		Inert		
WOODS PAVING COMPANY	322 FOYE WILSON ROAD		Inert		

102 BRANNEN STREET	102 BRANNEN STREET	Inert	
102 BRANNEN STREET	102 BRANNEN STREET	Inert	
MORRIS LUPTON PROPERTY	SE CORNER OF HWY 301 AND OLD REGISTER ROAD	Inert	
W.M. SHEPPARD LUMBER CO. HIGHWAY 80 INERT LF	EAST OF BROOKLET ON HWY 80 AT THE CITY LIMITS SIGN-SOUTH SIDE	Inert	
J. W. DELOACH INERT LANDFILL	SR 119	Inert	

^{*} all jurisdictions in plan use same disposal facilities

Source: Solid Waste program managers, Bulloch County and City of Statesboro, Georgia Environmental Protection Division

5.1.1 Assurance of 10-year capacity

Please see the attached letter in Appendix G from Broadhurst Landfill. The Landfill estimates approximately 12 years of capacity remaining. The letter states that waste coming from City of Statesboro and Bulloch County will be accepted. It should be noted that all waste from the Cities of Brooklet, Register, and Portal comes to the transfer station owned and operated jointly by the City of Statesboro and Bulloch County from which all waste is transported to Broadhurst landfill.

5.1.2 Contingency Strategy

In the event that Broadhurst Landfill is unable to accept material from Bulloch County, one of the following methods for disposing of waste would be used. Using current transportation methods, waste would be taken to Superior Landfill operated by Waste Management and located in Savannah. Other options for permanently disposing of waste include transporting it to Allendale Landfill in South Carolina or Candler County public landfill. This plan would be in effect within two business days of being needed.

5.1.3 Disaster Debris Management - Disposal Strategy

In the event of a disaster, waste would be handled using the aforementioned methods for collection and then transported to Broadhurst Landfill. The Statesboro-Bulloch County Airport would be used as a staging area until waste can be transported to Broadhurst. The public will be notified by recordings on government voicemail systems, postings on government websites, signage at recycling centers and transfer station and through local media.

5.2 Assessment of Disposal

^{**}inert, MSW, monofill, etc

Based on current capacity, the transfer station currently being used for MSVV has sufficient capacity to continue accepting waste over the next ten years. The inert site used by Bulloch County, however, has limited capacity. At current disposal rates, it is expected to have less than one year of remaining capacity. Once this site is filled, inert waste will likely be transported to the new site in development with twenty years of capacity.

5.3 Needs and Goals

<u>Goal</u>: Ensure sufficient disposal capacity to handle the amount of waste projected to be disposed of for the next ten years.

Strategy:

 Continue to transport waste to Broadhurst Landfill in Jesup, which has guaranteed capacity for the next ten years.

Goal: Ensure that existing and proposed solid waste handling facilities located in Bulloch County will not negatively impact the natural environment or public health and safety.

Strategy:

 Continue monitoring air and water quality at the closed Bulloch County Landfill on Lakeview road.

Section 6 Land Limitation Element

As in each section of this Solid Waste Management Plan, the cities of Statesboro, Register, Brooklet and Portal as well as unincorporated Bulloch County are included in the land limitations listed in this section.

6.1 Inventory Land Areas

6.1.1 Inventory Areas with Natural Environmental Limitations

Federal, state, and county policy contain restrictions on where solid waste facilities can be site, and, in some cases, the design required to site facilities in a specific area. Some of these restrictions are based on natural environmental land limitations. Bulloch County has a diverse range of topography, soils, and planned land use areas. The paragraphs and accompanying figures below describe each of the relevant environmental limitations.

- Floodplains DNR Rule 391-3-4-.05 (1)(d) stipulates any solid waste landfill located within the 100-year floodplain shall not restrict the flow of the 100-year flood, reduce temporary water storage capacity of the flood plain, or result in a washout of solid waste so as to pose a threat to human health of the environment.
- Wetlands DNR Rule 391-3-4-.05 (1)(e) prohibits the development of solid waste landfills in wetlands, as defined by the U.S. Army Corps of Engineers, unless evidence is provided by the applicant that use of the wetland has been permitted or otherwise authorized under all other applicable state and federal laws and rules.
- Water Supply Watersheds DNR Rule 391-3-16-.10(7)cl requires that at any location within a small water supply watershed, new solid waste landfills must have synthetic liners and leachate collections systems.
- Groundwater recharge areas The official code of Georgia (O.C.GA) Section 12-8-25.2 states that no permit shall be issued for municipal solid waste landfill if any part of the site is within two miles of an area that has been designated by the EPD Director as a significant groundwater recharge area unless such municipal solid waste landfill has a liner and leachate collection system and meets any other requirements as may be established by rules and regulations of the board or pursuant to other geological considerations as may be determined appropriate by the EPD Director.
- River Corridors DNR Rules prohibit the development of new solid waste landfills within protected river corridors.

Figure 6.1 below shows the water resources in Bulloch County. Areas highlighted in orange represent groundwater recharge areas. Areas highlighted in blue represent wetlands. The beige area is the Ogeechee River watershed and the pink area is the Canoochee River watershed.




Figure 6.2 shows the 100 year floodplain in Bulloch County.

6.1.2 Inventory Areas with Land Use Limitations

DNR Rule 391-3-4-.05(1)(a) requires that solid waste facility sites must conform to all local zoning/land use ordinances. Bulloch County has a zoning ordinance and accompanying map that specify approved uses for various districts within the county. The figure below shows the County's land use map, which is an illustrative description of the county's zoning ordinance and land use plan. More detailed descriptions for land limitations under this plan can be found in the Bulloch County Future Land Use Plan (adopted 2006) and the Bulloch County Zoning Ordinance.


Bulloch County Solid Waste Management Plan 0 Land Use Hadregud: 25593 te i

Figure 6.3 shows the zoning and future land use map for Bulloch County.

Other limitations apply to solid waste disposal facilities. State and Federal restrictions for siting solid waste facilities based on land uses include:

- National Historic Sites MSW landfills are not permitted with 5,708 yards of a National Historic Site (OCGA Section 12-8-25.1).
- Airport Safety DNR Rule 391-3-4-.05(1)© requires that new solid waste landfill units or lateral expansions of existing units shall not be within 5,000 feet of any runway planned or used for piston-type aircraft or within 10,000 feet of any runway planned or used for turbo-jet or piston-type aircraft. (See Figure 6.3)
- Surface Water Intake According to the Georgia DNR Rule 391-3-16-.01, unless
 there are no other feasible locations, solid waste landfills should not be located
 within two miles of a surface water intake for a public water source.
- Co-located landfills Section 12-8-25.4 of the OCGA states that no solid waste handling facility, excluding materials recovery facilities and composting facilities, can be sited on a site that falls within a two-mile radius of three or more solid waste landfills (including closed landfills that received waste on or after June 29, 1989).
- Political Subdivisions OCGA Section 12-8-25 prohibits the siting of an MSW landfill within one-half mile of another County's borders without the approval of that jurisdiction's governing authority. Bulloch County borders seven other counties.
- Private Recreational Camps OCGA Section 12-8-25.5 states that no permit shall be issued for any new municipal solid waste facility if any part of the premises proposed for permitting is within one mile of any private recreational camp operated primarily for the use by persons under 18 years of age and which camp has been so operated at its location for 25 years or more.
- Fault areas No such area is currently recorded as being present in Bulloch County. In the event that such an area is recorded by the appropriate regulatory organization, this plan will be amended to include limitations regarding solid waste management specific to this type of area.
- Seismic impact areas No such area is currently recorded as being present in Bulloch County. In the event that such an area is recorded by the appropriate regulatory organization, this plan will be amended to include limitations regarding solid waste management specific to this type of area.
- Unstable areas -- No such area is currently recorded as being present in Bulloch County. In the event that such an area is recorded by the appropriate regulatory organization, this plan will be amended to include limitations regarding solid waste management specific to this type of area.
- Protected mountains -- No such area is currently recorded as being present in Bulloch County. In the event that such an area is recorded by the appropriate regulatory organization, this plan will be amended to include limitations regarding solid waste management specific to this type of area.

Figure 6.4 shows Bulloch County Airport Safety restricted area. The area outlined in red represents a 10,000 foot buffer around the airport. There are no plans to expand the airport in the next ten years.



6.2 Local Procedures for Siting Solid Waste Facilities

Bulloch County has no plans to build or operate any solid waste handling facility within the ten-year planning period.

In addition, no proposed solid waste handling facility or facility expansion will be sited in Bulloch County without a letter from the County Commission or appropriate City Council stating that the proposed facility is consistent with the Solid Waste management Plan. Any applicant wishing to present a case for constructing such a facility will be required to cover expenses of developing plan and properly informing public based on the procedures listed in this plan and common practices for public notification followed by Bulloch County and/or the cities of Statesboro, Register, Portal, and Brooklet. The procedure for determining whether a proposed facility or facility expansion is consistent with the Solid Waste Management Plan is as follows:

- 1. At least 120 days prior to filing for a solid waste handling permit, or notifying EPD in the case of a solid waste handling facility that is permitted by rule, the applicant will submit to the governing body a written statement documenting the following:
 - a. How the proposed facility or facility expansion will meet the specific goals and/or needs identified in the Solid Waste Management Plan, including a description of:
 - i. The impact upon the collection capability within the county;
 - ii. The impact upon disposal capacity identified in the county; and
 - iii. The impact to the waste reduction and recycling efforts within the county, specifically how the proposed facility or facility expansion will further progress towards waste reduction.
 - b. How the proposed facility or facility expansion and its operation will impact the community. Specifically what will be:
 - i. The impact to vehicle traffic and public safety around the proposed facility and throughout the county;
 - ii. The impact on natural or cultural resources within the county;
 - iii. The impact to individual and business solid waste management rates; and
 - iv. The impact on the current solid waste management infrastructure with the county, both public and private.
 - c. The impact to the financial viability of the existing solid waste management system within the county.
 - d. Evidence that the proposed facility or facility expansion is sited in an area deemed suitable according to the criteria listed in the Plan.
 - e. Evidence that the proposed facility or facility expansion is sited in a location that is consistent with local zoning ordinances.
 - f. Evidence that the proper public notification was given, including notification of all adjacent property owners.
- 2. Within 60 days after this document is received, the County Commission and/or appropriate City Council will hold at least one public hearing on the proposed

- facility or facility expansion to gather input regarding the consistency of the facility with the Solid Waste Management Plan. This public hearing or hearings will be advertised according to local requirements regarding public notification of public hearings.
- 3. The governing body shall review the written documentation for consistency and consider public comment and determine whether the proposed facility or facility expansion is consistent with the Solid Waste Management Plan. Within 30 days of making their determination the governing body shall notify the facility owner/operator whether or not the proposed facility or facility expansion is consistent with the Plan. If the proposed facility is not consistent with the Plan, the developer may address the inconsistencies and resubmit their request for another review.

6.3 Assessment of Land Limitation

Bulloch County and the municipalities located within the county have a clear picture of the environmental and zoning limitations to siting solid waste facilities or facility expansions. More here?

6.4 Needs and Goals

<u>Goal</u>: To ensure that proposed solid waste handling facilities and expansions are developed to meet the needs of the county and the municipalities located within the county, are consistent with this Solid Waste Management Plan and with local government zoning ordinances, are compatible with surrounding land uses, and meet federal, state, and local environmental requirements.

Strategy:

- Keep all information about natural environmental limitations, zoning, and land use updated and available.
- Inform and educate potential developers about the procedures to determine consistency of proposed facilities with this Solid Waste Management Plan.
- Enforce the requirement that no solid waste handling facility be sited without a letter from the governing authority documenting its consistency with the Solid Waste Management Plan using the procedures described herein.

la la periodo de la companio de la c

Section 7 Education and Public Involvement Element

As in each element of this Solid Waste Management Plan, education and public involvement plans in this section include unincorporated Bulloch County, City of Statesboro, City of Brooklet, City of Portal and City of Register unless otherwise noted.

7.1 Inventory of Existing Public Education Programs and Public Involvement Opportunities

Bulloch County and the jurisdictions located within the county dedicate significant funding and staff resources to public education and involvement on solid waste issues. The county manages the community's recycling program and maintains information on recycling on behalf of all jurisdictions located within it. The County maintains educational signage at all recycling centers and unstaffed drop-off areas as well as providing information on the County's website and through the environmental management office.

Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register are all partners in funding, supporting and working in conjunction with Keep Bulloch Beautiful. Keep Bulloch Beautiful is governed by a 16-member board, which is comprised of representatives from each jurisdiction as well as the Chamber of Commerce. KBB employs an executive director, a recycling collector and a program coordinator. A summary of the programs and activities coordinated by Keep Bulloch Beautiful are outlined in the chart below.

Figure 7.1 Public Education and Involvement Activities and Programs

Program/Activity	Areas Covered	Operated By	Target Audience	Number of participants per year	description of impact
Recycling information on website	All	Bulloch County Environmental Management	General Public	65000	informs people on what, where, when and how to recycle
KBB recycling Website	All	Keep Bulloch Beautiful	General Public	65000	informs people on why, what, where, when and how to recycle
School Recycling Program	All	Keep Bulloch Beautiful	School Children	9000	Over 100,000 pounds collected annually
Business Recycling Assistance Program	All	Keep Bulloch Beautiful	local businesses	4000	educate, increase participation among employees of local businesses

Litter Prevention	All	Keep Bulloch Beautiful	General Public	65000	educate on how to be part of solution, reasons to prevent litter
webpage Tailgate Recycling	All	Keep Bulloch Beautiful	college students and GSU fans	80000	reduce waste, educate large audience about recycling
Bring One for the	Statesboro, Brooklet	Keep Bulloch Beautiful	General Public	250	educate, offer alternatives to disposing of yard waste
Volunteer Litter Cleanups	All	Keep Bulloch Beautiful	General Public	5000	educate about problem, participate in solution
Litter Hotline	All	Keep Bulloch Beautiful	General Public	1500	report litter, educate violators
Recycling Mobile	All	Keep Bulloch Beautiful	School Children	15000	educate students on solid waste and reduction
Neighborhoods at Work	All	Keep Bulloch Beautiful	General Public	4000	involve neighborhoods in preventing litter together
Cigarette Litter Prevention Program	Statesboro	Keep Bulloch Beautiful	General Public	250	educate, prevent cigarette litter
Rivers Alive	All	Keep Bulloch Beautiful	General Public	250	educate about litter and water resources connection, involve public as part of solution
Great American Cleanup	All	Keep Bulloch Beautiful	General Public	2500	educate about litter involve public as part of solution
America Recycles	All	Keep Bulloch Beautiful	General Public	500	educate public about recycling, encourage participation
Litter Prevention education materials	All	Keep Bulloch Beautiful	General Public	65000	education, prevention
Litter Free Events	All	Keep Bulloch Beautiful	General Public	50000	educate, provide convenient means to participate in solution

Storm Drain Stenciling	Statesboro	Ogeechee- Canoochee Riverkeeper	General Public	200	educate about litter and water resources connection, involve public as part of solution
LivinGreen	Statesboro	GSU	University Community	20000	educate, encourage participation in connection between energy and water use to solid waste reduction
Waste Reduction education programs	Statesboro	SAGE, GSEN, GSU	University Community	20000	educate, encourage participation in waste reduction efforts among college students, faculty, staff

7.2 Assess Adequacy of Environmental Education Initiatives

With Keep Bulloch Beautiful as the lead organization, Bulloch County has sufficient programs and activities in place to educate and involve the public on solid waste. Additional programs are continually being developed as resources and funds become available. Educational and public involvement programs have the full support of each jurisdiction's governing body as well as the general public.

7.3 Statement of Needs and Goals

Goal: Ensure that all residents in Bulloch County have access to and are routinely engaged by educational programs and information and opportunities to get involved in waste reduction and proper solid waste disposal.

Strategy:

- Maintain accurate and updated information on websites and in offices
- Continue outreach programs to various audiences
- Maintain proper signage at all recycling and waste disposal facilities
- Continue to produce educational literature

Section 8 Implementation Strategy

8.1 Summary of Needs and Goals

Waste Reduction

Goal: Increase volume and participation in recycling programs currently offered as well as those being developed while reducing the per capita disposal rate.

Strategy:

- Maintain current program operations
- Expand current program to provide additional opportunities for residents to reduce waste and recycle

Jurisdiction: Operated by Bulloch County government on behalf of all jurisdictions within the county

Collection

Goal: Provide residents living in all areas of the county with accessible and convenient means of properly disposing of trash and recyclables.

Strategy:

- Maintain citywide trash collection service in Statesboro
- Maintain recycling and trash drop-off centers throughout county (add additional centers as needed by population increase
- Continue to accept household trash and recyclables from private haulers operating outside Statesboro
- Encourage private haulers to offer curbside recycling programs using County's new single-stream processing facility

Jurisdiction: City of Statesboro, City of Portal and City of Brooklet have exclusive collection operations within each jurisdiction. Bulloch County operates collection of drop-off containers in all jurisdictions except Statesboro. Residents and businesses in Register and the unincorporated areas of the county have independent contracts with private haulers.

Disposal

Goal: Ensure sufficient disposal capacity to handle the amount of waste projected to be disposed of for the next ten years as well as ensuring environmental safety of disposal practices.

Strategy:

 Continue to transport waste to Broadhurst Landfill in Jesup, which has guaranteed capacity for the next ten years. Jurisdiction: Transportation to Broadhurst landfill for permanent disposal is operated by the City of Statesboro on behalf of all jurisdictions within Bulloch County.

Land Limitation

Goal: To ensure that proposed solid waste handling facilities and expansions are developed to meet the needs of the county and the municipalities located within the county, are consistent with this Solid Waste Management Plan and with local government zoning ordinances, are compatible with surrounding land uses, and meet federal, state, and local environmental requirements.

Strategy:

- Keep all information about natural environmental limitations, zoning, and land use updated and available.
- Inform and educate potential developers about the procedures to determine consistency of proposed facilities with this Solid Waste Management Plan.
- Enforce the requirement that no solid waste handling facility be sited without a letter from the governing authority documenting its consistency with the Solid Waste Management Plan using the procedures described herein.

Jurisdiction: Due to the small size of the cities of Brooklet, Portal, and Register, land limitation issues are handled through Bulloch County on behalf of the aforementioned jurisdictions as well as the unincorporated areas of the county. The City of Statesboro's zoning and land limitation policies compliment those adopted by Bulloch County.

Education and Public Involvement

Goal: Ensure that all residents in Bulloch County have access to and are routinely engaged by educational programs and information and opportunities to get involved in waste reduction and proper solid waste disposal.

Strategy:

- · Maintain accurate and updated information on websites and in offices
- Continue outreach programs to various audiences
- Maintain proper signage at all recycling and waste disposal facilities
- Continue to produce educational literature

Jurisdiction: Keep Bulloch Beautiful is housed in Bulloch County government but operates public education efforts and involvement on behalf of all jurisdictions within the county. The City of Statesboro also handles a limited amount of public education for collection services.

8.2 Implementation Strategy/Short Term Work Program

The chart below describes the implementation strategy and timeline for this Solid Waste Management Plan. The first five years of the implementation strategy represent the short-term work plan. Plans for the latter five years will be revisited in 2012 to update plans and create the short-term work plan for 2013-2018. (see attached spreadsheet)

Implementation Strategy

Program/Activity	ik it		-	Years Program/Activity Takes Place	ogram,	'Activit	y Takes	Place				Responsible	Estimated	Funding Source
	2008	2009 2010		2011	2012	2013	2014	2015	2016	2017	2018			
Waste Reduction Element Needs/goals:								7/ /L						
Maintain operation of drop-off recycle centers	×	×	×	×	×	×	×	×	×	×	×	Bulloch County	\$400,000/yr	General Fund, recycling revenue
Increase participation in drop-off recycling program		×	×			7144	* (pa.		200			Bulloch County	\$250,000	SPLOST, recycling revenue
Expand processing facility to accept more volume, Single-stream, accept regional material	×	×										Bulloch County	\$750,000	SPLOST, DCA grant
Increase participation in school, business recycling programs	×	×	×	x 2/		101	7 1 54					Keep Bulloch Beautiful, Bulloch County	\$30,000/yr	recycling revenue, solid waste fund, misc. grants and donations
Maintain recycling collection, Implement voluntary curbside recycling in Statesboro		×	×	×	×	×	×	×	×	×	×	Bulloch	\$50,000/yr	General Fund, recycling revenue
Collection Element Needs/goals:							4-0							
Maintain citywide collection in City of Statesboro	×	×	×	×	×	×	×	×	×	×	×	City of Statesboro	Bobby?	Bobby?
Maintain drop-off centers thoughout County	×	×	×	×	×	×	×	×	×	×	×	Bulloch County	Bob?	General Fund
Continue accepting waste from private haulers through transfer station	×	×	×	×	×	×	×	×	×	×	×	City of Statesboro	transfer station budget?	source of budget? Solid waste revenue, general fund?
Expand transfer Station to more efficiently accept current and predicted volumes	7,40, 2	×	×			A Total		<i>ett</i>				City of Statesboro	Bobby?	Bobby?

recycling revenue, solid waste fund, misc. grants and donations		P Bobby?	? Mickey?		ed General Fund for both jurisdictions		recycling revenue, solid waste fund, misc. grants and donations	your on General Fund here	do e a Bobby? ofr
included in other operating budgets		Bobby?	Mickey?	-7.63	as needed		\$120,000/yr	Bob - put your education budget in here	Bobby - do you have a budget ofr
Keep Bulloch Beautiful, Bulloch County		City of Statesboro	City of Statesboro		Bulloch County, City of Statesboro		Keep Bulloch Beautiful	Bulloch County	City of Statesboro
×		×	×		×		×	×	×
×		×	×		×		×	×	×
×		×	×		×		×	×	×
×		×	×		×		×	×	×
×		×	×		×		×	×	×
×		×	×		×		×	×	×
×		×	×		×		×	×	×
×		×	×		×		×	×	×
×		×	×		×		×	×	×
×		×	×		×		×	×	×
		×	×		×		×	×	×
Encourage private haulers to offer curbside recycling programs	Disposal Element Needs/goals:	Transport material to Broadhurst Landfill	Monitor closed landfill	Land Limitation Element Needs/goals:	land limitation plans, procedures up to date	Education, Public Involvement Element Needs/goals:	Maintain, update KBB programs and activities	Maintain educational information through Environmental Management Office	Maintain educational information through the City's solid waste department

Section 9 Appendix

Appendix A: Bulloch County resolution
Appendix B: City of Statesboro resolution
Appendix C: City of Brooklet resolution
Appendix D: City of Portal resolution
Appendix E: City of Register resolution
Appendix F: Public Hearing Notices

Appendix G: Broadhurst Landfill Capacity Assurance Letter

Appendix H: Clean Community Ordinance

THE BULLOCH COUNTY BOARD OF COMMISSIONERS

RESOLUTION #08-

APPROVE SOLID WASTE MANAGEMENT PLAN TO BE REVIEWED BY STATE

WHEREAS, The Georgia Comprehensive Solid Waste Management Act of 1990 enacted by the Georgia General Assembly mandated that each of Georgia's counties and cities prepare and Solid Waste Management Plan every ten years; and update the Solid Waste Management Short Term Work Program every five; and

WHEREAS, Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register have completed an updated Solid Waste Management Plan; and

WHEREAS, Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register have complied with the Rules and Georgia Department of Community Affairs Minimum Planning Standards and Procedures for Solid Waste Management (Chapter 11-4-3) including public participation requirements;

NOW, THEREFORE, BE IT RESOLVED by the Bulloch County Board of Commissioners that the document entitled Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register Solid Waste Management Plan, which includes the updated Short Term Work Program, may be transmitted to the Coastal Georgia Regional Development Center for its formal review and then to the Georgia Department of Community Affairs for final approval before adoption by the Bulloch County Board of Commissioners.

SO RESOLVED ON THIS 15th DAY OF APRIL, 2008.

RECORD OF ACTION TAKEN

COMMISSIONER	AYE	NAY	ABSTAIN	ABSENT	OTHER
Nevil (Chair)	X				
Thompson	X				
Gibson	X		er e		
Jackson					Absent
Simmons					Atsent
Rushing	X				
Tankersley	X		7		
TOTAL					

CERTIFICATE OF RESOLUTION

The undersigned hereby certifies that I am the Chairman of the Board of Commissioners for Bulloch County, Georgia; that the attached hereto is a true copy of the Resolution duly adopted by the governing body of the County, at a meeting duly held on the 15th day of 2008 at the Bulloch County Annex at which a quorum was present and acting throughout, and that it has not been rescinded or modified and is now of full force and effect.

Garrett Nevil, Chairman

Bulloch County Board of Commissioners

The undersigned hereby certifies that I am the County Manager for Bulloch County, Georgia (the "County"); that the attached hereto is a true copy of the Resolution duly adopted by the governing body of the County, at a meeting duly held on the /sh day of April 2008 at the Bulloch County Annex at which a quorum was present and acting throughout, and that it has not been rescinded or modified and is now of full force and effect.

Attest

GIVEN under the seal of the County, this 15th day of 40ril 2008

(SEAL)

STATE OF GEORGIA COUNTY OF BULLOCH

THE BULLOCH COUNTY BOARD OF COMMISSIONERS

RESOLUTION # 2008 - 25

TO ADOPT THE 2008-2018 JOINT SOLID WASTE MANAGEMENT PLAN

WHEREAS, the Georgia Comprehensive Solid Waste Management Act of 1990 enacted by the Georgia General Assembly mandated that each of Georgia's counties and cities prepare a Solid Waste Management Plan every ten years, and update the Solid Waste Management Short Term Work Program every five years; and

WHEREAS, Bulloch County and the cities of Statesboro, Brooklet, Portal, and Register have completed an updated Solid Waste Management Plan; and

WHEREAS, Bulloch County and the cities of Statesboro, Brooklet, Portal, and Register have complied with the rules of the Georgia Department of Community Affairs for Minimum Planning Standards and Procedures for Solid Waste Management (Chapter 110-4-3 of the Georgia Administrative Code), including public participation requirements; and

WHEREAS, the Coastal Georgia Regional Development Center and the Georgia Department of Community Affairs have reviewed and given final approval of the Plan;

NOW THEREFORE, BE IT RESOLVED by the Bulloch County Board of Commissioners that the 2008-2018 Joint Solid Waste Management Plan for Bulloch County and the cities of Statesboro, Brooklet, Portal, and Register, which includes the updated Short Term Work Program, is hereby adopted by the Bulloch County Board of Commissioners.

RESOLUTION APPROVED AND ADOPTED this 5th day of August, 2008.

BOARD OF COMMISSIONERS OF BULLOCH COUNTY, GEORGIA

A. Garret Nevil, Chairman

Maggie Fitzgerald, Clerk

RESOLUTION # 2008-18: A RESOLUTION AUTHORIZING THE SUBMISSION OF THE BULLOCH COUNTY AND CITIES OF STATESBORO, BROOKLET, PORTAL, AND REGISTER SOLID WASTE MANAGEMENT PLAN INCLUDING THE UPDATED SHORT TERM WORK PROGRAM TO THE COASTAL GEROGIA REGIONAL DEVELOPMENT CENTER FOR FORMAL REVIEW AND TO THE GEORGIA DEPARTMENT OF COMMUNITY AFFAIRS FOR FINAL APPROVAL

WHEREAS, The Georgia Comprehensive Solid Waste Management Act of 1990 enacted by the Georgia General Assembly mandated that each of Georgia's counties and cities prepare a Solid Waste Management Plan every ten years; and update the Solid Waste Management Short Term Work Program every five years; and

WHEREAS, Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register have completed an updated Solid Waste Management Plan; and

WHEREAS, Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register have complied with the Rules and the Georgia Department of Community Affairs Minimum Planning Standards and Procedures for Solid Waste Management (Chapter 11-4-3) including public participation requirements;

NOW THEREFORE BE IT RESOLVED by the Mayor and City Council of the City of Statesboro, Georgia this 15th day of April, 2008 that the document entitled Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register Solid Waste Management Plan, which includes the updated Short Term Work Program, may be transmitted to the Coastal Georgia Regional Development Center for its formal review and then to the Georgia Department of Community Affairs for final approval before adoption by the Statesboro City Council.

This Resolution shall be and remain in full force and effect from and after its date of adoption.

Adopted this 15th day of April, 2008.

CITY OF STATESBORO, GEORGIA

By: William S. Hatcher, Mayor

Attest: Judy M McCorkle City Clerk

RESOLUTION # 2008-27: A RESOLUTION TO ADOPT THE SOLID WASTE MANAGEMENT PLAN INCLUDING THE UPDATED SHORT TERM WORK PROGRAM FOR BULLOCH COUNTY AND THE CITIES OF STATESBORO, BROOKLET, PORTAL, AND REGISTER AS SUBMITTED TO THE GEORGIA DEPARTMENT OF COMMUNITY AFFAIRS

WHEREAS, The Georgia Comprehensive Solid Waste Management Act of 1990 enacted by the Georgia General Assembly mandated that each of Georgia's counties and cities prepare a Solid Waste Management Plan every ten years; and update the Solid Waste Management Short Term Work Program every five years; and

WHEREAS, the City of Statesboro along with Bulloch County and the Cities of Brooklet, Portal, and Register have compiled, reviewed and modified an update to the Solid Waste Management Plan; and

WHEREAS, the City of Statesboro and Bulloch County and the Cities of Brooklet, Portal, and Register have complied with the Rules of Georgia Department of Community Affairs Minimum Planning Standards and Procedures for Solid Waste Management (Chapter 110-4-3) including public participation requirements;

NOW THEREFORE BE IT RESOLVED by the Mayor and City Council of the City of Statesboro, Georgia this 5th day of August, 2008 that the document entitled 2008 – 2018 Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register Solid Waste Management Plan, which includes the updated Short Term Work Program, be officially approved and adopted.

This Resolution shall be and remain in full force and effect from and after its date of adoption.

Adopted this 5th day of August, 2008.

CITY OF STATESBORO, GEORGIA

3/: Joe R. Brannen, Mayor Pro tem

Attest: Judy M. McCorkle. City Clerk

RESOLUTION

- WHEREAS, The Georgia Comprehensive Solid Waste Management Act of 1990 enacted by the Georgia General Assembly mandated that each of Georgia's counties and cities prepare and Solid Waste Management Plan every ten years; and update the Solid Waste Management Short Term Work Program every five; and
- WHEREAS, Bulloch County and the Cities of Statesboro; Brooklet, Portal, and Register have completed an updated Solid Waste Management Plan; and
- WHEREAS, Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register have complied with the Rules and Georgia Department of Community Affairs Minimum Planning Standards and Procedures for Solid Waste Management (Chapter 11-4-3) including public participation requirements;
- NOW, THEREFORE, BE IT RESOLVED by the Brooklet City Council that the document entitled Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register Solid Waste Management Plan, which includes the updated Short Term Work Program, may be transmitted to the Coastal Georgia Regional Development Center for its formal review and then to the Georgia Department of Community Affairs for final approval before adoption by the Brooklet City Council.

SO RESOLVED ON THIS / DAY OF DE 2008.

Joseph Grooms, Mayor

City of Brooklet

ATTEST

City Clerk

BROOKELT CITY COUNCIL

RESOLUTION #08-__

ADOPT SOLID WASTE MANAGEMENT PLAN

- WHEREAS, The Georgia Comprehensive Solid Waste Management Act of 1990 enacted by the Georgia General Assembly mandated that each of Georgia's counties and cities prepare and Solid Waste Management Plan every ten years; and update the Solid Waste Management Short Term Work Program every five; and
- WHEREAS, Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register have completed an updated Solid Waste Management Plan; and
- WHEREAS, Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register have complied with the Rules and Georgia Department of Community Affairs Minimum Planning Standards and Procedures for Solid Waste Management (Chapter 11-4-3) including public participation requirements;
- WHEREAS, The Coastal Georgia Regional Development Center and Georgia Department of Community Affairs have reviewed and given final approval of the Plan;
- NOW, THEREFORE, BE IT RESOLVED by the members of the Brooklet City Council that the document entitled Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register Solid Waste Management Plan, which includes the updated Short Term Work Program, may be adopted by the Brooklet City Council.

SO RESOLVED ON THIS 17 DAY OF 12 2008.

CERTIFICATE OF RESOLUTION

toseph Grooms, Mayor

City of Brooklet

The undersigned hereby certifies that I am the Clerk for City of Brooklet, Georgia (the "City") that the attached hereto is a true copy of the Resolution duly adopted by the governing body of the City, at a meeting duly held on the 1 th day of 2008 at the Brooklet City Hall at which a quorum was present and acting throughout, and that it has not been rescinded or modified and is now of full force and effect.

City Clerk

GIVEN under the seal of the Town, this / 7 th day of July 2008

(SEAL)



Joe A. Grooms, Mayor

ATTEST

Belle Gay

City Clerk

RESOLUTION

- WHEREAS, The Georgia Comprehensive Solid Waste Management Act of 1990 enacted by the Georgia General Assembly mandated that each of Georgia's counties and cities prepare and Solid Waste Management Plan every ten years; and update the Solid Waste Management Short Term Work Program every five; and
- WHEREAS, Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register have completed an updated Solid Waste Management Plan; and
- WHEREAS, Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register have complied with the Rules and Georgia Department of Community Affairs Minimum Planning Standards and Procedures for Solid Waste Management (Chapter 11-4-3) including public participation requirements;
- NOW, THEREFORE, BE IT RESOLVED by the Portal City Council that the document entitled Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register Solid Waste Management Plan, which includes the updated Short Term Work Program, may be transmitted to the Coastal Georgia Regional Development Center for its formal review and then to the Georgia Department of Community Affairs for final approval before adoption by the Portal City Council.

SO RESOLVED ON THIS DAY OF 48 2008.

Larry Motes, Mayor

City of Portal

ATTEST

EVA PITTS

City Clerk

PORTAL CITY COUNCIL

RESOLUTION #08-09

ADOPT SOLID WASTE MANAGEMENT PLAN

- WHEREAS, The Georgia Comprehensive Solid Waste Management Act of 1990 enacted by the Georgia General Assembly mandated that each of Georgia's counties and cities prepare and Solid Waste Management Plan every ten years; and update the Solid Waste Management Short Term Work Program every time; and
- WHEREAS, Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register have completed an updated Solid Waste Management Plan; and
- WHEREAS, Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register have compiled with the Rules and Georgia Department of Community Affairs Minimum Planning Standards and Procedures for Solid Waster Management (Chapter 11-4-3) including public participation requirements;
- WHEREAS, The Coastal Georgia Regional Development Center and Georgia Department of Community Affairs have reviewed and given final approval of the Plan:
- NOW, THEREFORE, BE IT RESOLVED by the members of the Portal City Council that the document entitled Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register Solid Waste Management Plan, which includes the updated Short Term Work Program, may be adopted by the Portal City Council.

SO RESOLVED ON THIS 21 DAY OF Juy, 2008.

CERTIFICATE OF RESOLUTION

The undersigned herby certifies that I am the Mayor of the City of Portal, Georgia; that the attached hereto is a true copy of the Resolution duly adopted by the governing body of the City, at a meeting duly held on the 21 th day of July 2008 at the Portal City Hall at which a quorum was present and acting throughout, and that it has not been rescinded or modified and is now of full force and effect.

City of Portal

JUL-22-2008 23:59 From: CITY OF PORTAL

The undersigned herby certifies that I am the Clerk of the City of Portal, Georgia; that the attached hereto is a true copy of the Resolution duly adopted by the governing body of the City, at a meeting duly held on the 21 th day of 3008 at the Portal City Hall at which a quorum was present and acting throughout, and that it has not been rescinded or modified and is now of full force and effect.

Eva Pitts, Clerk City of Portal

GIVEN under the seal of the City, this 2/ th day of Jucy 2008

Larry Motes, Mayor City of Portal

Eva Pitts, Clerk City of Portal Register, Georgia to transmit the Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register Solid Waste Management Plan.

WHEREAS, the Georgia Comprehensive Solid Waste Management Act of 1990 enacted by the Georgia General Assembly mandated that each of Georgia's counties and cities prepare and submit a Solid Waste management Plan every ten years; and update the Solid Waste Management Short Term Work Program every five; and

WHEREAS, Bulloch County and the Cities of Statesboro, Brooklet, Portal, and the Town of Register have completed and updated Solid Waste Management Plan; and

WHEREAS, Bulloch Count y and the Cities of Statesboro, Brooklet, Portal, and the Town of Register have complied with the Rules and Georgia Department of Community Affairs Minimum Planning Standards and Procedures for Solid Waste Management (Chpater 11-4-3) including public participation requirements;

NOW, THEREFORE, BE IT RESOLVED by the Register Town Council that the document entitled Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register Solid Wste Management Plan, which includes the updated Short Term Work Program, may be transmitted to the Coastal Georgia Regional Development Center for its formal reviw and then to the Georgia Department of Community Affairs for final approval before adoption by the Register Town Council.

SO RESOLVED, this 15th day of April, 2008.

Kathleen O'Grady, Mayor of Register

Mandi Cody Pilz, Town Clerk



Resolution of the Town of Register, Georgia to Adopt the 2008 Solid Waste Management Plan.

WHEREAS, the Georgia Comprehensive Solid Waste Management Act of 1990 enacted by the Georgia General Assembly mandated that each of Georgia's counties and cities prepare and adopt a Solid Waste Management Plan every ten years; and

WHEREAS, the Georgia General Assembly mandated that such plan be updated by the adoption of a Solid Waste Management Short Term Work Program every five years; and

WHEREAS, Bulloch County, the City of Statesboro, the City of Portal, the Town of Brooklet, and the Town of Register have complied with the mandate of the Georgia General Assembly and the rules of the Department of Community Affairs Minimum Planning Standards and Procedures for Solid Waste Management (Chapter 11-4-3), including the required public participation elements, and prepared such a plan entitled the Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register Solid Waste Management Plan; and

WHEREAS, the Coastal Georgia Regional Development Center and the Georgia Department of Community Affairs have reviewed and given final approval of the Plan;

NOW THEREFORE, BE IT RESOLVED by the members of the Register Town Council that the document entitled Bulloch County and the Cities of Statesboro, Brooklet, Portal, and Register Solid Waste Management Plan, which includes the Short Term Work Program, be approved and adopted by the Register Town Council.

SO RESOLVED this 22nd day of July, 2008.

Kathleen O'Grady

Mayor, Town of Register

Mayor fortem

Attest:

Mandi Cody Pilz Clerk, Town of Register

Certificate of Resolution:

I, Kathleen O'Grady, hereby certify that I am the Mayor of the Town of Register, Georgia; that the attached hereto is a true and correct copy of the Resolution of the Town of Register, Georgia to Adopt the 2008 Solid Waste Management Plan duly adopted by the governing body of the municipality at a meeting held on the 22nd day of July, 2008 at the Register Community Center at which a quorum was present and acting throughout, and that it has not been rescinded or modified and is now of full force and effect.

Knthloen O'Gredy Lisa R. Ryles Mayor, Town of Register, Georgia Mayor Pro Term

Attest: V (With Wind)
Mandi Cody Pilz

Clerk, Town of Register, Georgia

ARTICLE IV. CLEAN COMMUNITY REGULATIONS*

*Editor's note: An ordinance adopted Sept. 6, 2007(1), enacted provisions designated as §§ 8-51--8-133, and have been treated as superseding the former §§ 8-51--8-133, which pertained to the same subject matter and derived from an ordinance adopted June 1, 1993, and Ord. No. 1996-6, adopted March 5, 1996.

Cross references: Board of health, § 8-26 et seq.; emergency management, 6-1 et seq.; solid waste collection containers, § 10-61 et seq.

DIVISION 1. GENERALLY

Sec. 8-51. General provisions.

It shall be unlawful for any person to trespass on the rights of others through the neglect of property by causing or allowing unsightly litter, foul odor or potentially dangerous devices to remain on or emanate from the property, or to discard, abandon or cause such on public property or others' private property. Provided however, odors generated by legitimate, commercial agricultural activities shall not be deemed to constitute a violation of this article. The provisions of the article shall apply to the unincorporated areas of the county. (Amend. of 11-6-07(1))

Sec. 8-52. Definitions.

For the purpose of this article, the following terms, phrases, words and their derivations shall have the meaning given herein. When not inconsistent with the context, words used in the present tense include the future, words in the plural number include the singular number, and words in the singular number include the plural number. The word "shall" is always mandatory and not merely directory. The following definitions shall apply in the interpretation and the enforcement of this article:

Abandoned manufactured home or Abandoned mobile home means a manufactured home or mobile home for which no valid permit has been issued by the developmental services division and which is not connected to an approved sewage system and/or is disconnected from electrical service. Provided, however, that a manufactured home or mobile home on the lot of a location that is lawfully in the manufactured home sales business shall be exempt from this definition. Biomedical waste means any solid waste which contains pathological waste, biological waste, cultures and stacks of infectious agents and associated biological waste, contaminated animal carcasses, including body parts, their bedding and other waste from such animals, chemotherapy waste, discarded medical equipment and parts, not including expendable supplies and materials which have not been contaminated.

Building materials means any materials such as lumber, brick, plaster, gutters or other substances accumulated as a result of repairs or additions to existing buildings, construction of new buildings or demolition or existing structures.

Bulk container means a metal container of not less than four cubic yards nor larger than 42 cubic yards and constructed so that it can be emptied mechanically by specially equipped trucks.

Business trash means any waste accumulation of dust, paper and cardboard, excelsior, rags or other accumulations, other than garbage or household trash, which are usually attendant to the operation of stores, offices and similar businesses.

County means the County of Bulloch.

Commercial establishment means any retail, manufacturing, wholesale, institutional, religious, governmental or other nonresidential establishment at which garbage or trash may be generated. Commercial waste means any waste generated by a commercial establishment.

County manager means the chief administrative officer of Bulloch County.

Debris means sand, dirt, broken brick, blocks, broken pavement or other similar materials suitable for fill. Said term shall not include household garbage or other types of refuse such as wood or wood products which are subject to decomposition or decay.

Disposal site means an area, location, tract of land or facility used or intended to be used for the disposal of solid waste or a facility, or putrescible waste, hazardous waste or other waste, except it shall not include the land or facility used for the disposal of solid waste or other waste from a single-family dwelling in which the owner, occupant or lessee of said land or facility resides. Environmental manager means the county officer designated by the county manager as the person responsible for administration and enforcement of this article.

Garbage means the by-product of animal or vegetable foodstuffs resulting from the handling, preparation, cooking and consumption of food, or other matter which is subject to decomposition, decay, putrefaction or the generation of noxious or offensive gases or odors, or which during or after decay, may serve as a breeding or feeding material for flies, insects or animals.

Hazardous refuse means materials such as poison, acids, caustics, chemicals, infected materials, offal, fecal matter and explosives.

Household trash means every waste accumulation of paper, sweepings, dust, rags, bottles, cans or other matter of any kind, other than garbage, which is usually attendant to housekeeping. Industrial waste means all waste, including solids, semisolids, sludges and liquids, created by factories, processing plants or other manufacturing enterprises.

Junk means any motor vehicle, machine, appliance, scrap metal or other scrap material that is in a condition which prevents its use for the purpose for which it was originally manufactured.

Junk vehicle means any wrecked or non-operable vehicle that does not bear a current license plate.

Litter means garbage, refuse, waste materials or any other discarded, used or unconsumed substance which is not handled as specified herein.

Loading and unloading areas means space or area used by any moving vehicle for the purpose of receiving, shipping and transporting goods, wares, commodities and persons.

Multiple unit means any duplex, apartment, group of apartments or condominium used for dwelling places of more than one family.

Nuisance means anything that causes hurt, inconvenience, or damage to another and the fact that the act done may otherwise be lawful shall not keep it from being a nuisance. The inconvenience complained of shall not be fanciful, or such as would affect only one of fastidious taste, but it shall be such as would affect an ordinary, reasonable man.

Person means individual, firm, company, partnership, corporation or association.

Refuse means solid waste accumulations consisting of garbage, household trash, yard trash and business trash as herein defined.

Refuse receptacle means a metal or plastic container for refuse, of substantial construction, with tight-fitting lids, and provided with handles and/or wheels sufficient for safe and convenient handling. Such receptacles shall have a capacity of not less than 22 gallons nor more than 32 gallons and shall be kept in serviceable condition at all times.

Scavenging means to search through trash, debris, or otherwise discarded material.

Scrap tire means an automobile or truck tire that is no longer suitable for its original intended purpose because of damage, defect or wear.

Single residential unit means any dwelling place occupied by one family.

Small dead animals means cats, dogs, small household pets and other animals of similar size.

Used tire means a tire which has a minimum of two and thirty-two hundredths of an inch of road tread and which is still suitable for its original intended purpose.

Yard trash means waste accumulation of tree branches, tree limbs, parts of trees, bushes, shrubbery, cuttings or clippings, or other usually created as refuse in the case of trees or bushes. Waste means solid waste and liquid waste.

(Amend. of 11-6-07(1))

Sec. 8-53. Authority, duty of the chief administrative officer.

The collection, transportation and disposal of refuse shall be under the supervision and control of the county manager who may delegate this authority to the environmental manager. The environmental manager shall have the authority to establish routes and days of collection, types and locations of refuse containers, and such other matters, pertaining to the collection, transportation and disposal of refuse as he may find necessary and to change and modify the same.

(Amend. of 11-6-07(1))

Sec. 8-54. Collection to be by county.

Licenses . It shall be unlawful for any person to collect solid waste within the county, except from his own residence or business or industrial property, without first obtaining a proper permit or license for such business operation from the Georgia Department of Natural Resources and Bulloch County.

(Amend. of 11-6-07(1))

Sec. 8-55. Receptacles and containers required.

It shall be required of every person in possession, charge or control of any place in or from which building materials, business trash or industrial waste is accumulated or produced to provide and at all times to keep in a suitable place readily accessible to the county collection crews or private collection agencies, adequate and suitable receptacles and containers capable of holding all such waste materials which would ordinarily accumulate between the times of successive collections. The environmental manager shall determine the quantity and location of said receptacles and shall determine where said receptacle and containers are serviceable. (Amend. of 11-6-07(1))

Sec. 8-56. Receptacles and containers to be safe.

All receptacles and containers as required hereunder shall have said construction and design and shall be maintained in good and serviceable condition at all times. Any receptacles or containers which do not conform to the provisions of this article or which have ragged or sharp edges or any

other defects likely to hamper or injure the person collecting the contents hereof or the public generally, after proper notice, has not been replaced, may be removed as refuse. (Amend. of 11-6-07(1))

Sec. 8-57. Pre-collection practices.

- (a) Biomedical waste. No biomedical waste shall be placed in a container for collection by the county.
- (b) Refuse . All refuse shall be placed and maintained in containers as specified herein.
- (c) Garbage. All garbage being placed in containers for collection shall have drained from it all free liquid, and should be wrapped, bagged or enclosed in paper or plastic material.
- (d) Household trash. All household trash shall be drained of all liquids prior to its deposit in refuse receptacles. Household trash shall be combined with garbage.
- (e) Injurious trash items. All waste material of an injurious nature such as broken glass, light bulbs, sharp pieces of metal, fluorescent tubes and television tubes shall be securely wrapped to prevent injury to the collection crews.
- (f) Hazardous refuse and building materials. No hazardous refuse shall be placed in any receptacle used for collection by the county nor shall the same be collected by the county.
- (g) Yard trash. No yard trash shall be placed in any receptacle used for collection of garbage by the county nor shall the same be collected by the county except in containers so designated for yard trash.

(Amend. of 11-6-07(1))

Sec. 8-58. Storing of refuse and trash.

All accumulations of refuse and trash shall be stored or placed for collection in accordance with the following provisions:

- (1) Public street and private property. No person shall place any accumulations of refuse or trash in any street, median strip, alley or other public place of travel, nor upon any private property except as stated herein.
- (2) Blockage of storm drain. No person shall place any refuse, trash, refuse receptacles or containers on, upon or over any storm drain, or so close thereto as to be drawn by the elements into same.
- (3) Unauthorized accumulations. Any accumulations of refuse or trash items on any lot, property, premises, public street, alley or other public or private place not permitted by this article, is hereby declared to be a public nuisance and is prohibited. Failure of owner or occupant to remove and correct any such accumulations shall be deemed a violation of this article.
- (4) Junk . It shall be deemed unlawful for any person to place or leave outside any building or dwelling any dilapidated furniture, appliance, machinery, equipment, building material, junk motor vehicle or other item which is either in a wholly or partially rusted, wrecked, junked, dismantled or inoperative condition, and which is not completely enclosed within a building or dwelling. Any such item or items which remain on the property of the occupant for a period of ten days after notice of violation of this section shall be presumed to be abandoned and subject to being removed from the property by the county without further notice with the reasonable costs of said removal to be paid by the owner to the environmental manager, and same shall constitute a lien on the property until paid. This shall not apply to county-approved junk dealers or county-approved establishments engaged in the repair, rebuilding, reconditioning or salvaging of equipment or furniture.

- (5) Appliances. It shall be unlawful for any reason to leave outside any building in a place accessible to children any appliance, refrigerator or other container of any kind which has an airtight snap lock or similar device or without first removing the lock or door from said appliances, refrigerator or container unless it is crated, strapped or locked to such an extent that it is impossible for a child to obtain access to any airtight compartment thereof.
- (6) Scavenging . Scavenging from any collection container is prohibited, and it shall be unlawful and in violation of this article for any person except as fully authorized by the board of commissioners to enter, examine and sift through the contents of, or remove any matter from any collection container.

(Amend. of 11-6-07(1))

Sec. 8-59. Scattering of refuse and littering prohibited.

- (a) It shall be unlawful for any person or persons to dump, deposit, throw or leave or to cause or permit the dumping, depositing, placing, throwing or leaving of litter on any public or private property in the unincorporated areas of the county or any waters in the unincorporated areas of the county, unless:
- (1) The property is designated by the state or by the county for the disposal of litter and the person is authorized by the proper public authority to use such property;
- (2) The litter is placed into a litter receptacle or container installed on such property; or
- (3) The person is the owner or tenant in lawful possession of such property or has first obtained consent of the owner or tenant in lawful possession or unless the act is done under the personal direction of the owner or tenant, all in a manner consistent with the public welfare and consistent with other provisions of this division, as well as other applicable laws, ordinances and resolutions.
- (b) In addition to the other penalties authorized by this division, in the sound discretion of the judge of a court in which conviction is obtained, the person may be directed to pick up and remove from any public beach, public park, public right-of-way, or, with the prior permission of the legal owner or tenant in lawful possession of such property, any private property upon which it can be established by competent evidence that he has deposited litter, any and all litter deposited thereon by anyone prior to the date of the execution of sentence, and/or the court may publish the names of persons convicted of violating subsection (a) of this section.
- (c) Whenever litter is thrown, deposited, dropped or dumped from any motor vehicle, boat, airplane or other conveyance in violation of subsection (a) of this section, it shall establish a rebuttable presumption that the operator of the conveyance has violated this division.
- (d) Except as provided in subsection (a) of this section, whenever any litter which dumped, deposited, thrown or left on public or private property in violation of this section which is discovered to contain any article or articles, including, but not limited to, letters, bills, publications or other writings which display the name of a person thereon in such a manner as to indicate that the article belongs or belonged to such person, there shall be established a rebuttable presumption that such person has violated this division.
- (e) It shall be unlawful for any vehicle transporting loose materials within the county to transport same without suitable covers. This subsection shall not apply to the transportation of poultry or livestock or silage or other feed grain used in the feeding of poultry or livestock.
- (f) It shall be unlawful for any person to throw or deposit any refuse, building material, building material waste, cement sludge, asphalt sludge or other substances accumulated as a result of

construction, repairs to existing facilities demolition of existing structures on or into any public or private road, shoulder of any public or private road or public or private ditch. (Amend. of 11-6-07(1))

Sec. 8-60. Handbills and advertising matter.

(a) It shall be unlawful to place in or on any automobile in the county any handbill, circular, pamphlet, poster, postcard or other literature except with the expressed permission of the owner or occupant of such automobile.

(b) It shall be unlawful for any person to place on private property any handbill, circular, pamphlet, poster, postcard or other literature, except with the expressed permission of the owner of the property or intended recipient. This section shall not apply to multi-page printed

publications.

(c) It shall be unlawful for any person to tack, post or nail any paper, metal, wood or other signs for advertising material of any character on any telegraph, telephone or electric light pole, on any street or alley within the county.

(Amend. of 11-6-07(1))

Sec. 8-61. Commercial establishments.

(a) All commercial establishments, all multi-unit developments as defined in section 10-65 of the Code of Ordinances of Bulloch County and all manufactured home communities as defined by section 9-1 of the Code of Ordinance of Bulloch County, Georgia shall store their refuse in containers as specified herein so as to eliminate wind-driven debris and unsightly litter in and about their establishments. Approved methods of containerization include refuse receptacles, bulk containers and detachable containers. Spillage and overflow shall be immediately cleaned up by said establishment when and as it occurs.

(b) All commercial establishments shall have a bulk container unless their refuse and trash can be suitably contained in refuse receptacles approved by the county.

(c) It shall be unlawful for any person to put household garbage, trash or any other waste in a commercial dumpster within the county without permission from the owner or lessee of said dumpster or the owner of the commercial establishment.

(d) It shall be unlawful for any person or persons to remove any article, trash or other material from any commercial dumpster without permission from the owner.

(e) It shall be unlawful for any person to scatter material from a commercial dumpster around the commercial dumpster.

(Amend. of 11-6-07(1))

Sec. 8-62. Loading and unloading areas.

All loading and unloading areas shall be provided with refuse receptacles for loose debris, paper, packaging materials and other trash. The number of containers necessary for each area shall be as required to maintain clean, neat and sanitary premises as directed by the environmental manager. The owner of the premises and the occupant thereof shall jointly and severally maintain surveillance to insure that all litter is placed in the proper container and the area is kept clean. (Amend. of 11-6-07(1))

Sec. 8-63. Parking lots.

- (a) Obligation to furnish receptacles. All parking lots and establishments with parking lots shall provide refuse receptacles distributed within the parking area. The environmental manager shall have the authority to determine the number and types of receptacles necessary to provide proper containerization. Such receptacles shall be weighted or attached to the ground as necessary to prevent spillage. It shall be the responsibility of the owner or the manager of the parking lots to collect the refuse and trash deposited in such containers and store this material in an approved location as hereinabove defined.
- (b) Obligation to use receptacles. It shall be the obligation of all persons using the parking areas to use such refuse receptacles or containers as hereinabove provided for the purpose intended, and it shall be unlawful for any person or persons to dump, scatter or throw upon any such parking lot, any refuse, garbage or trash of any kind.

 (Amend. of 11-6-07(1))

Sec. 8-64. Construction sites and demolition sites.

All construction and demolition contractors shall provide on-site refuse receptacles, bulk containers or detachable containers for loose debris, paper, building material waste, scrap building materials and other trash procured by those working on the site. The site shall be kept in a litter-free condition. The number of refuse receptacles, bulk containers or detachable containers shall be determined by the size of the job. Dirt, mud, construction materials or other debris deposited upon any public or private property as a result of construction or demolitions shall be removed by the contractor upon completion of the construction.

(Amend. of 11-6-07(1))

Sec. 8-65. Collection practices.

- (a) Bulk container. Any commercial establishment that furnishes and maintains containers suitable for handling by county equipment may be serviced by the county as herein stated, provided that said container shall be of sufficient size as specified and be approved for collection. Said containers shall at all times be kept clean, neat, painted and in a good state of repair. Service shall be discontinued to establishments failing to maintain containers appropriately. Establishments utilizing bulk containers are responsible for repairing said containers for service; no service shall be given those establishments permitting objects, obstructions or vehicles to hinder in any way the servicing of the said container. Cleaning up spilled materials shall be the responsibility of the property owner or occupant.
- (b) Holidays. Collections shall not be made on the following holidays unless otherwise specified by the environmental manager: New Year's Day, Fourth of July, Thanksgiving Day and Christmas Day.
- (c) Industrial waste. Industrial waste shall be collected, removed and disposed of by the operator of the factory, plant or enterprise creating or causing same.
- (d) Hazardous refuse. No hazardous refuse shall be placed in any receptacle used for collection of refuse by the county.
- (e) Building materials . The county shall not be responsible for the collection or hauling of building materials originating from private property preliminary to, during or subsequent to the construction of new buildings, alterations or additions to existing buildings of whatever type or from demolition of existing structures. Such material shall be removed by the owner of the property or by the contractor. Contractors shall not deposit building materials at county

collection centers such as recycling centers and open or unmanned container sites, but shall transport building materials to an approved landfill or transfer station for disposal.

(f) No biomedical waste shall be placed in a county receptacle.

- (g) Lawn care and landscaping waste. The county shall not be responsible for the collection or disposal of lawn care or landscaping waste generated by the activities of a lawn care or landscaping business, regardless of whether such waste is generated on residential, commercial or government property. Such waste shall be removed by the lawn care or landscaping business or by the owner of the property. Such waste shall not be deposited at county collection centers such as recycling centers and open container sites, but shall be transported by the lawn care or landscaping business or property owner to an approved landfill or transfer station for disposal.

 (h) Commercial waste. With the exception of recyclable materials, commercial waste shall not
- (h) Commercial waste. With the exception of recyclable materials, commercial waste shall not be deposited at county collection centers such as recycling centers and open container sites, but shall be transported by the owner of the commercial establishment or his authorized agent to an approved landfill or transfer station for disposal.

 (Amend. of 11-6-07(1))

Sec. 8-66. Special refuse disposal.

- (a) Contagious disease refuse. The removal of clothing, bedding or other refuse from homes or other places where highly infectious diseases have prevailed shall be performed under the supervision and direction of the county health department. Such refuse shall not be placed in containers for county collection.
- (b) Hypodermic instruments. No person shall dispose of or discard any hypodermic syringe, hypodermic needle or any device for making hypodermic injections before first breaking, disassembling, destroying or otherwise rendering inoperable and incapable of reuse, such hypodermic syringe, needle, instrument or device, and without safeguarding the disposal thereof, by wrapping or securing same in a suitable manner so as to avoid the possibility of causing injury to the collection persons.
- (c) Cardboard boxes and cartoons. Prior to depositing refuse for collection in authorized containers or receptacles or in commercial containers, the person disposing of any such boxes or cartons or the person in charge of the premises shall collapse all cardboard boxes and cartons.
- (d) Scrap and used tires. Pursuant to authority granted in O.C.G.A. § 12-8-40.1, no person shall collect, store or transport scrap and used tires for processing or disposal in contradiction to current state law or this chapter.
- (1) No person may store more than 100 scrap or used tires, combination of the two, except those persons specifically authorized by the foregoing cited state law. Any person, other than those specifically exempted, found storing in excess of 100 scrap or used tires shall be deemed to be in violation of this chapter and be subject to enforcement and penalties as provided in this chapter.
- (2) Any person disposing of scrap or used tires must take the tires to either a state authorized and licensed business accepting scrap and used tires for disposal, further processing, reconditioning or recycling. Passenger vehicle tires may be disposed of at county recycling centers, provided that the same person shall not be allowed to dispose of more than six passenger vehicle tires per day at a county recycling center. Scrap and used tires may not be buried, burned, dumped or disposed of in any manner other than as outlined within this section and chapter. Any person disposing of such tires in any manner contrary to these provisions shall be deemed to be

in violation of this chapter and shall be subject to enforcement and penalties as provided in this chapter.

(Amend. of 11-6-07(1))

Sec. 8-67. Unsecured loads.

All persons who desire to haul refuse over the county road shall use a vehicle provided with a cover and operate it so as to prevent refuse from being dropped, blown or spilled. (Amend. of 11-6-07(1))

Sec. 8-68. Responsibility of owners and agents.

The owners or agents, tenants or lessees of all residential units and commercial establishments shall be responsible for compliance with this division.

(Amend. of 11-6-07(1))

Sec. 8-69. Maintenance of property.

- (a) Property . All owners or occupants of property shall maintain their property in a litter-free condition.
- (b) Sweeping into sidewalks or streets. No person shall sweep into or deposit in any street or sidewalk the accumulation of litter from any building or property.

(Amend. of 11-6-07(1))

Secs. 8-70--8-80. Reserved.

DIVISION 2. COMMUNITY IMPROVEMENT

Sec. 8-81. Nuisance designated.

It shall be unlawful for any person to create a nuisance on his property or property occupied by him, or to allow a nuisance to remain on his property or property occupied by him. Nuisances, as contemplated herein, shall include but shall not be limited to dead animals, stagnant water, decayed vegetables or fruits, filthy privies or stables, anything having an offensive odor, accumulations of junk, abandoned or junk vehicles, abandoned mobile homes, improper or malfunctioning septic systems, or anything that causes injury or damage to the health, life, or property of any other person; provided, however, odors generated by legitimate, commercial agricultural activities shall not be deemed to constitute a nuisance under this section. (Amend. of 11-6-07(1))

Sec. 8-82. Duty of person responsible.

- (a) It shall be unlawful for any person to maintain any premises, including vacant lots or land, upon which trash, junk, abandoned or junk vehicles, abandoned or unsafe manufactured homes or mobile homes, garbage or miscellaneous refuse is permitted to cause to accumulate in any manner which is, or may become a nuisance, or cause injury to the health or welfare of residents in the vicinity or may injure neighboring property. Drive-in restaurants and other food establishments that permit carry-out food service shall maintain at all times on their premises sufficient receptacles for the disposal of trash, garbage and miscellaneous refuse.
- (b) It shall be unlawful for any person to maintain, cause or permit uncut grass or weeds on any property under such circumstances that the grass or weeds are breeding places for insects, rodents or reptiles or is a fire hazard.

(c) If the person responsible for correcting the conditions named above has not acted to correct the violation after notice to him by the environmental manager, his assistants or deputies may enter upon the premises where the violation occurs and remove the trash, junk, abandoned or junk vehicles, abandoned or unsafe manufactured or mobile homes, garbage or refuse, or the grass or weeds and the county shall assess costs incurred by it, and this shall be a charge against the person responsible, and shall be a lien against the property from which the trash, garbage or refuse has been removed, or the grass or weeds have been cut. As used in this provision, the term "person responsible" means both the owner of the property where the violation occurs and, if distinct, the person or persons causing the violation, all of whom shall be jointly and severally liable for correcting any violations and for any costs incurred by the county in correcting the violations.

(Amend. of 11-6-07(1))

Sec. 8-83. Enforcement, remedies and penalties for violation.

- (a) All law enforcement agencies, officers and officials of the state or any political subdivision thereof including county marshals, or any enforcement agency, officer or any official of any commission of the state or any political subdivision thereof is authorized, empowered and directed to enforce compliance with this division.
- (b) In the event that any person, firm or corporation violated any provision of this division, the county attorney or other appropriate authority of the county may in addition to other remedies, institute injunction, mandamus or other appropriate action or proceeding to prevent such unlawful act or to correct or abate such violation.
- (c) Any person who shall do anything prohibited by this division or who shall fail to do anything required by this division shall be subject to punishment as provided in section 1-11 of this Code and O.C.G.A. § 36-1-20.

(Amend. of 11-6-07(1))

Secs. 8-84--8-90. Reserved.

DIVISION 3. ABANDONED MOTOR VEHICLES

Sec. 8-91. Abandonment unlawful.

It shall be unlawful to abandon any motor vehicle on any public street, road or public grounds, or upon any private property, and it shall be unlawful for any person owning private property to abandon or to knowingly permit the abandonment thereupon of any motor vehicle. (Amend. of 11-6-07(1))

Sec. 8-92. Abandoned vehicles defined.

For the purpose of this division, a motor vehicle shall be determined to have been abandoned in any of the following circumstances:

- (1) If it is partially dismantled or wrecked and it is left on a street, road, alley or sidewalk for a period of five days or longer.
- (2) If it is left on private property without the consent of the owner, occupant or lessees thereof for 48 hours or longer.
- (3) If it is left on any public street, alley or sidewalk for seven days or longer.
- (4) If it is partially dismantled, wrecked or incapable of self-propulsion and is left by the owner on his own property for 30 days or longer.

(Amend. of 11-6-07(1))

Sec. 8-93. Removal.

- (a) Any abandoned motor vehicle may be removed to a storage area for safekeeping by or under the direction of the sheriff's department of the county or other person, firm or corporation so designated by the county. Written notice by mail of such removal shall be promptly given to the registered owner of the vehicle.
- (b) No abandoned vehicle shall be removed from privately owned premises without the written consent of the owner, lessee or occupant of the premises, unless the same has been found by the environmental manager or his designee to be a health or safety hazard or constitutes a nuisance. (Amend. of 11-6-07(1))

Sec. 8-94. Disposition of abandoned vehicles.

- (a) The owner of any removed abandoned vehicles, before obtaining possession thereof, shall pay to the environmental manager all reasonable costs, incidental to the removal, storage and locating of the owner.
- (b) Should such owner fail or refuse to pay the costs, or should his identity or whereabouts be unknown and unascertainable after a search by the environmental manager or designated agent and after notice as herein prescribed, the stored vehicle may be sold after 20 days' notice has been given to the Georgia Department of Motor Vehicles, 20 days' notice to any lien holder of record, and after the vehicle has been held for not less than 30 days and notice of sale has been published once a week for two weeks in the official organ of the county.
- (c) The abandoned vehicle shall be sold in the manner set forth below.
- (d) A vehicle of an appraised value of less than \$100.00 may be disposed of by any means in the discretion of the environmental manager, including private sale. A vehicle of an appraised value of \$100.00 or more shall be sold at public sale after notice as provided above, on the first Tuesday of any month in the manner and at such time as sheriff's sales are held.
- (e) The proceeds of any sale shall be forwarded to the clerk of the county who shall pay from the proceeds of said sale of costs of removal, storage, investigation as to ownership and sale, and liens in that order. If, after the sale, the ownership at the time of the removal is established satisfactorily to the clerk, the owner shall be paid so much of the proceeds as remains after the payment of the foregoing costs and liens. Otherwise, any remaining proceeds shall be forfeited and deposited in the general fund of the county.

(Amend. of 11-6-07(1))

Secs. 8-95--8-110. Reserved.

DIVISION 4. DISPOSAL SITES

Sec. 8-111. Use authorized; regulation.

All domestic and other acceptable refuse shall be delivered and deposited at authorized disposal sites in accord with the directions and orders of the environmental manager or his representative in charge of operations.

(Amend. of 11-6-07(1))

Sec. 8-112. Designation.

(a) Public sites approved for the disposal of refuse shall be designated by appropriate signs.

(b) Such sites shall be maintained in use until permanently closed, at which time additional authorized sites shall be opened and publicized by posting and through the press. (Amend. of 11-6-07(1))

Sec. 8-113. Operating hours.

Authorized public disposal sites shall be operated at such times as may be designated and posted by the environmental manager.

(Amend. of 11-6-07(1))

Sec. 8-114. When use authorized; ownership of waste.

All materials delivered and deposited for disposal on the grounds of disposal sites shall be the property of the county.

(Amend. of 11-6-07(1))

Sec. 8-115. Scavenging prohibited.

No person shall be permitted to scavenge or reclaim any refuse which has been delivered to a public disposal site for disposal.

(Amend. of 11-6-07(1))

Sec. 8-116. Permit and acceptance required.

It shall be unlawful for any person, firm or corporation to dump, or to cause to be dumped, any waste anywhere in the unincorporated area of the county, except at an approved landfill or transfer station, or at a collection site operated by the county.

(Amend. of 11-6-07(1))

Sec. 8-117. Identification; presumed evidence.

If any of the matter or material dumped in violation of the provisions of section 8-116 above can be identified as having last belonged to, been in the possession of, sent to or received by, or to have been the property of any person, firm or corporation prior to its being dumped as prohibited herein, this identification shall be presumed to be prima facie evidence that the owner dumped, or caused to be dumped, this matter and material in violation of this division.

(Amend. of 11-6-07(1))

Sec. 8-118. General maintenance.

It shall be the duty and responsibility of the owner of any private disposal site to keep the site in an orderly condition and maintained so as not to be a public nuisance or a menace to public health and to comply with all state and local permitting requirements.

(Amend. of 11-6-07(1))

Sec. 8-119. Right to enter to inspect.

The environmental manager or his designated representative or authorized representative of the department of natural resources, shall be permitted to enter private disposal sites at any time during normal business hours for free and unhindered inspections to determine compliance with this chapter and all other pertinent laws and regulations.

(Amend. of 11-6-07(1))

Sec. 8-120. Burning prohibited.

- (a) No person shall set fire to, or burn any paper or other refuse deposited at any disposal site or on the grounds thereof.
- (b) No garbage or other materials, from which offensive odors emanate during combustion, shall be burned outside any building.

(Amend. of 11-6-07(1))

Secs. 8-121--8-130. Reserved.

DIVISION 5. ENFORCEMENT

Sec. 8-131. Service of warning notice.

A warning notice may be served either on the person or business by leaving same at the residence or business of the person being notified or by certified mail. An executed certified mail receipt by the person or business being notified or the agent of such person or business shall be deemed sufficient service and notice of a warning notice.

(Amend. of 11-6-07(1))

Sec. 8-132. Service of citation.

Service of a citation for any violation of this article shall be by personal service as prescribed by state law.

(Amend. of 11-6-07(1))

Sec. 8-133. Penalties.

All violators of the provisions of this article shall, upon conviction of said violation, be subject to the penalties as provided in section 1-11 of this Code.

(Amend. of 11-6-07(1))

Secs. 8-134--8-150. Reserved.



July 11, 2008

Brooke Carney, Director Keep Bulloch Beautiful 17315 Highway 301 North Statesboro, GA 30458

Re: Bulloch County 2008 - 2018 Joint Solid Waste Management Plan Update

Dear Brooke:

We have received notification from the Department of Community Affairs (DCA) regarding the Bulloch County and the Cities of Brooklet, Portal, Register, and Statesboro Joint Solid Waste Management Plan (SWMP). DCA has determined that the SWMP is in compliance with the Minimum Standards and Procedures for Solid Waste Management. The letter is attached for your reference.

A Regional Review hearing was held on May 15, 2008 at the CGRDC office in Statesboro. No comments were received in advance of the hearing, and no one other than CGRDC staff was in attendance at the hearing.

Bulloch County and the Cities of Brooklet, Portal, Register, and Statesboro must now adopt the SWMP. After adoption, please forward copies of the signed resolutions to my attention, along with two (2) hard copies of the final adopted SWMP document, as well as an electronic version. The CGRDC will forward this information to DCA, who will then notify the local governments of their eligibility for solid waste grants, loans, and permits.

If you have any questions, please contact me at (912) 262-2870.

Sincerely,

Tricia Reynolds, AICP

Director of Planning & Government Services

TR/bk


Enclosure

c: Chairman J. Garrett Nevil, Bulloch County Commission Mayor William S. Hatcher, City of Statesboro Mayor Joseph A. Grooms, Town of Brooklet Mayor Larry Motes, Town of Portal Mayor Kathleen O'Grady, Town of Register



June 17, 2008

Mr. Allen Burns, Executive Director, Coastal Georgia Regional Development Center Post Office Box 1917 Brunswick, Georgia 31521



Dear Allen:

Our staff has reviewed the information for the 2008 – 2018 Solid Waste Management Plan for Bulloch County and the Cities of Brooklet, Portal, Register and Statesboro. The Solid Waste Management Plan is in compliance with the Minimum Planning Standards and Procedures for Solid Waste Management. To maintain eligibility for solid waste permits, grants, and loans, Bulloch County and the Cities of Brooklet, Portal, Register and Statesboro must adopt the 2008 – 2018 Solid Waste Management Plan as soon as possible.

In order to complete the planning cycle, please forward a copy of the adoption resolutions along with a copy of the adopted Solid Waste Management Plan to our office. Once we receive these documents, we will send notification to Bulloch County and the Cities of Brooklet, Portal, Register and Statesboro of their eligibility for solid waste grants, loans, and permits.

Sincerely,

Mike Greaton, Assistant Commissioner Planning and Environmental Division

MG/jk





Implementation Strategy

			Sport efficients vencent statebile fills processing	adhiqaideach yaetamilikd	coan captiled ov stravateni it griftspan				
						acharate in		thost Mesure a through translay track	
								×	
	\$10								
				darthed reading	doctions			by yild chadesafe.it	
				VON US			WARK, BOLD		060,000,62
					Annasida hrind iens mel			bns sunivertidmos 120,96	

Maintain educational information through the City's solid waste department	Maintain educational information through Environmental Management Office	Maintain, update KBB programs and activities	Education, Public Involvement Element Needs/goals:	land limitation plans, procedures up to date	Land Limitation Element Needs/goals:	Monitor closed landfill	Transport material to Broadhurst Landfill	Disposal Element Needs/goals:	Encourage private haulers to offer curbside recycling programs
×	×	×				×	×		
×	×	×		×		×	×		
×	×	×		×		×	×		×
×	×	×		×		×	×		×
×	×	×		×		×	×		×
×	×	×		×		×	×		×
×	×	×		×		×	×		×
×	×	×		×		×	×		×
×	×	×		×		×	×		×
×	×	×		×		×	×		×
×	×	×		×		×	×		×
×	×	×		×		×	×		×
City of Statesboro	Bulloch County	Keep Bulloch Beautiful		Bulloch County, City of Statesboro		City of Statesboro	City of Statesboro		Keep Bulloch Beautiful, Bulloch County
included in collection budget	none	\$120,000/yr		as needed		\$108,000/yr	\$865,000/yr		included in other operating budgets
N/A	General Fund	recycling revenue, solid waste fund, misc. grants and		General Fund for both jurisdictions		SPLOST	SPLOST		recycling revenue, solid waste fund, misc. grants and donations

					wayii ilozanyelei sravistrosmyelei sravistrosmyelei	
	× 1					×
	X					
						in opposition rectantless
			of charticumits and sub-tay dind			